



# A New DC Muon Beam Source: MuSIC - Status and Prospects -

Akira SATO

Department of Osaka University

$\mu$

International Workshop on Neutrino Factories, Super Beams and Beta Beams: NuFact2012  
July 23-28, 2012, Williamsburg, VA USA

20+5 min

# ● Contents

- Overview of the MuSIC
  - Concept
  - Status and schedule
  - Expected muon yield by simulation
  - Design
- Results from beam tests
  - Muon collection efficiency
  - high current operation
- Summary


# Overview

# What is the MuSIC?

- **MuSIC**
  - The world's most efficient DC muon beam source using the first pion capture solenoid system.
    - 400W proton beam from RCNP ring cyclotron
  - Design muon intensity :
    - $10^{8-9} \mu/\text{s}$  @392MeV,  $1 \mu\text{A}$  proton beam
  - One on the main projects of RCNP program in a new program of Research Center for Subatomic Science.
- **Technical points of the MuSIC**
  - The first pion capture solenoid system
    - muon collection efficiency  $> 10^3$  than conventional muon beam lines
  - A muon transport solenoid with dipole field


# Muon collection at the MuSIC

## Conventional muon beam line




## MuSIC

MuSIC, COMET/Mu2e, PRISM,  
Neutrino factory,  
Muon collider




Large solid angle & thick target

# The Final Layout of MuSIC



# MUSIC@RCNP, Osaka Univ.

Research Center of Nuclear Physics (RCNP),  
Osaka University, Japan




- RCNP has two cyclotrons. A proton beam with 392MeV,  $1\ \mu\text{A}$  is provided from the Ring Cyclotron (up to  $5\ \mu\text{A}$  in near future).
- The MuSIC is in the largest experimental hall, the west experimental hall.

# History of MuSIC Projects


- **2009JPY**
    - Construction of a proton beam line, pion capture system, and transport solenoid (up to 36 deg)
  - **2010JPY**
    - Commissioning of super-conducting magnets of pion capture and transport
    - 2010, Jul. : 1<sup>st</sup> beamtest ( $I_{\text{proton}}=3\text{nA}$ )
      - proton beam hits the production target,
      - Every system worked successfully,
      - observed secondary particles at the end of the transport solenoid
    - 2011, Feb. : 2<sup>nd</sup> beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muon beam was counted from their life spectrum,
  - **2011JYP**
    - 2011, Jun. : 3rd beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muon life measurements with a higher statistics
      - muonic-Xray measurements
        - the design muon collection efficiency was confirmed by the measurement
    - 2011, Oct. : 4th beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muonic-Xray measurements with a higher statistics
      - measurement of neutron flux and energy around the MuSIC
    - 2012, Mar. : East side radiation shielding blocks were located.
  - **2012JYP**
    - 2012, Jun 18-22 : 5th beam test
      - measurements for muon energy and spatial distribution
      - the system was operated with a high current proton beam ( $I_{\text{proton}}=\sim 1\text{ microA}$ )
- 
- Construction**
- Commissioning**
- Muon collection efficiency**
- High current operation**

# Schedule



# Muon beam from MuSIC by simulation

by g4beamline, QGSP\_BERT,  $E_p=392\text{MeV}$



- Changing magnitude and direction of the dipole field, we can select charge and momentum of the beam.

# Muon beam from MuSIC by simulation

by g4beamline, QGSP\_BERT,  $E_p=392\text{MeV}$

$B_y$ (T)	$N(\mu^+)$ for $I_p=1\mu\text{A}$	$N(\mu^-)$ for $I_p=1\mu\text{A}$	$N(\mu^+) / N(\mu^-)$
-0.08	0	$1E+08$	0
-0.06	0	$9E+07$	0
-0.04	$6E+04$	$5E+07$	$1E-03$
-0.02	$7E+05$	$2E+07$	$3E-02$
0	$2E+07$	$4E+06$	$5E+00$
0.02	$1E+08$	0	-
0.04	$3E+08$	0	-
0.06	$4E+08$	0	-
0.08	$4E+08$	0	-


The proton beam current will be upgraded to  $5\mu\text{A}$  in near future.

# Examples of Muon Science at MuSIC


- **Particle Physics :**
  - search for  $\mu \rightarrow \text{eee}$  (muon LFV)
    - DC continuous beam is critical
- **Nuclear Physics :**
  - nuclear muon capture (NMC)
  - pion capture and scattering
- **Chemistry :**
  - chemistry on pion/muon atoms
- **Materials Science :**
  - $\mu$ SR (a  $\mu$ SR apparatus is needed)
- **Accelerator / Instruments R&D**
  - (for PRISM/neutrino factory/muon collider) :
    - Superconducting solenoid magnets
    - FFAG, RF
    - cooling methods
    - muon acceleration, deceleration, and phase rotation

# Details

# MuSIC: Present Layout





# MuSIC@RCNP-West Hall (~2012 Feb)



# Superconducting Magnets

## Superconducting Coils

Conductor	Cu-stabilized NbTi
Cable diameter	$\Phi 1.2$ mm
Cu/NiTi ratio	4
RRR ( $R_{293K}/R^{10K}$ at 0T)	230-300



Operation current	145 A
Max field on axis	3.5 T
Bore	$\Phi 900$ mm
Length	1000 mm
Inductance	400 H
Stored energy	5 MJ
Quench back heater (Cu wire)	1.2 mm dia. $\sim 1\Omega @ 4K$

Solenoid coil of the capture solenoid



Operation current	145 A
Max field on axis	2.0 T
Bore	$\Phi 480$ mm
Length	200 mm x 8 coils
Inductance	124 H
Stored energy	1.4 MJ
Quench back heater (Cu wire)	1.3 mm dia. $\sim 0.05\Omega /coil @ 4K$

Solenoid coil of the transport solenoid

Operation current	115 A
Max field on axis	0.04 T
Bore	$\Phi 460$ mm
Length	200 mm/coil
Inductance	0.04 H/coil
Stored energy	280 J/coil



Dipole coil of the transport solenoid

# Proton Beam Monitoring on the Target



Upstream

Downstream



Target at the center of the capture solenoid.

# Proton Beam on the target






# Beam Tests

# History of MuSIC Projects

- **2009JPY**
    - Construction of a proton beam line, pion capture system, and transport solenoid (up to 36 deg)
  - **2010JPY**
    - Commissioning of super-conducting magnets of pion capture and transport
    - 2010, Jul. : 1<sup>st</sup> beamtest ( $I_{\text{proton}}=3\text{nA}$ )
      - proton beam hits the production target,
      - Every system worked successfully,
      - observed secondary particles at the end of the transport solenoid
    - 2011, Feb. : 2<sup>nd</sup> beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muon beam was counted from their life spectrum,
  - **2011JYP**
    - 2011, Jun. : 3rd beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muon life measurements with a higher statistics
      - muonic-Xray measurements
        - the design muon collection efficiency was confirmed by the measurement
    - 2011, Oct. : 4th beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muonic-Xray measurements with a higher statistics
      - measurement of neutron flux and energy around the MuSIC
    - 2012, Mar. : East side radiation shielding blocks were located.
  - **2012JYP**
    - 2012, Jun 18-22 : 5th beam test
      - measurements for muon energy and spatial distribution
      - the system was operated with a high current proton beam ( $I_{\text{proton}}=\sim 1\text{ microA}$ )
- 
- Construction**
- Commissioning**
- Muon collection efficiency**
- High current operation**


# Setup: muon life and muonic-X-ray



# Results from muonic X-ray



Number of negative muons at the 36 deg exit for  $1\mu\text{A}$  proton beam

	beam test	simulation
Num. of muons [1/sec]	$(1.7 \pm 0.3) \times 10^8$	$1.4 \times 10^8$



# Muon Life



- Stopping target : Cu




# Operation with 400W proton beam

# History of MuSIC Projects

- **2009JPY**
    - Construction of a proton beam line, pion capture system, and transport solenoid (up to 36 deg)
  - **2010JPY**
    - Commissioning of super-conducting magnets of pion capture and transport
    - 2010, Jul. : 1<sup>st</sup> beamtest ( $I_{\text{proton}}=3\text{nA}$ )
      - proton beam hits the production target,
      - Every system worked successfully,
      - observed secondary particles at the end of the transport solenoid
    - 2011, Feb. : 2<sup>nd</sup> beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muon beam was counted from their life spectrum,
  - **2011JYP**
    - 2011, Jun. : 3rd beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muon life measurements with a higher statistics
      - muonic-Xray measurements
        - the design muon collection efficiency was confirmed by the measurement
    - 2011, Oct. : 4th beam test ( $I_{\text{proton}}=\sim 4\text{nA}$ )
      - muonic-Xray measurements with a higher statistics
      - measurement of neutron flux and energy around the MuSIC
    - 2012, Mar. : East side radiation shielding blocks were located.
  - **2012JYP**
    - 2012, Jun 18-22 : 5th beam test
      - measurements for muon energy and spatial distribution
      - the system was operated with a high current proton beam ( $I_{\text{proton}}=\sim 1\text{ microA}$ )
- 
- Construction**
- Commissioning**
- Muon collection efficiency**
- High current operation**




# CX8 Position



# Terminal Temperature

$$T = T_0 + (T_f - T_0)(1 - e^{-t/\tau})$$

**$T_f \sim 4.4\text{K}$**



The coil temperature up to  $\sim 6.5\text{K}$  is acceptable.  
MuSIC can work with 400W proton beam.


# Summary

- A new intense DC muon beam line is under construction at RCNP, Osaka University. This is the first muon facility which adopts a superconducting pion capture system. It would provide  $>10^8$ muons/sec with a 400W proton beam.
- The pion capture solenoid and a 36 deg. of transport solenoid have been build.
- Five beam tests with a low current proton beam have been performed. The results from muon life and muonic X-ray measurements conclude more than  $10^8$  muons/sec with 392MeV,  $1\mu\text{A}$  proton is achievable at the MuSIC.
- Finally, the system successfully have been operated with 392meV- $1\mu\text{A}$  proton beam in June, 2012.
- The MuSIC also can be considered as one of the very important R&D programs for not only the COMET project, and also PRISM/PRIME and Neutrino factories and Muon collider.

# A Future Plan of RCNP: 1MW proton cyclotron


2023~???

		The present MuSIC	A future plan
Proton cyclotron	proton beam energy	400 MeV	400 MeV
	proton beam current	1 $\mu$ A	<b>2.5 mA</b>
	proton beam power	400 W	$\times 2.5 \times 10^3$ <b>1 MW</b>
MuSIC system	production target	Graphite, L=20cm	$\times 2$ Tungsten, 16cm
	Solenoid field	3.5 Tesla	$\times 1.4$ 5.0 Tesla
Muon beam	$\mu^+$ yield	$1 \times 10^8$ /sec	<b><math>7 \times 10^{11}</math> /sec</b>
	$\mu^-$ yield	$1 \times 10^8$ /sec	<b><math>7 \times 10^{11}</math> /sec</b>




# Backup Slides

# パイオン捕獲システム





- 標的を強磁場中に置き、パイオンを捕獲
- ミューオンビーム上流側から陽子ビームを入射すると超伝導コイルが大量の放射線を浴びる
- 陽子ビームを超伝導コイルの隙間から入射
- 標的からの放射線を防ぐためソレノイド内部にシールドを挿入
- 磁場勾配を利用してパイオンを輸送ソレノイドへ導く


すべての超伝導コイルは液体ヘリウムを使わず、GM冷凍機で冷やす  
→ 低コスト・運転が楽 → 放射線による核発熱を1W以下に抑える必要あり。



巻枠計測線取付位置








# パイオン捕獲システム：仕様

Conductor	Cu-stabilized NbTi
Cable diameter	$\phi 1.2\text{mm}$
Cu/NbTi ratio	4
RRR (R293K/R10K at 0T)	230-300
Operation current	145A
Max field on axis	3.5T
Bore	$\phi 900\text{mm}$
Length	1000mm
Inductance	400H
Stored energy	5MJ
Quench back heater	1.2mm dia.
Cu wire	$\sim 1\Omega @ 4\text{K}$





# ミューオン輸送ソレノイド

世界初の実用：  
 $\cos\theta$ 巻き超伝導双曲電磁石

## Solenoid coils

Operation current	145A
Field on axis	2T
Bore	$\phi 480$ mm
Length	200mm x8Coils
Inductance	124H
Stored energy	1.4MJ
Quench back heater Cu wire	1.3mm dia. ~0.05Ω/Coil@4K




## Correction dipole coils

Coil layout	Saddle shape dipole
	6 layers
	528 turns (1 set)
Current	115A (Bipolar)
Field	0.04T
Aperture	$\phi 460$ mm
Length	200mm
Inductance	0.04H/Coil
Stored Energy	280J/Coil


# パイオン捕獲システム：放射線環境

- 27cm厚 ステンレスシールド
- コールドマス核発熱 0.6W
  - 0.4W in coil (~1ton)
  - 0.2W in coil support
- 超伝導コイルの被爆量 ~10kGy/year
- ターゲット: 100W
- シールド: 50W
  
- 中性子フラックス
  - $5 \times 10^{18}$  neutrons/m<sup>2</sup>/year
  - 超伝導線のアルミ導体の劣化は起こらない。
    - $10^{20}$ - $10^{22}$  n/m<sup>2</sup>
  - ダイオードはソレノイドから離し、制御盤内に設置。







# Refrigeration

- Conduction cooling by GM cryocoolers
- Can be cooled down within 1 week with pre-cooling by LN<sub>2</sub>
- Pion capture solenoid
  - 4K: 1W+nucl. heating 0.6W
  - 300K→40K: 50W
    - GM 1<sup>st</sup> stage
  - 3 x GM cryocooler
    - 1.5Wx2+1Wx1 @4K
    - 45Wx2+44W @40K
- Transport solenoid
  - 4K: 0.8W
  - 300K→40K : 50W
    - GM 1<sup>st</sup> stage
  - 2 x Cryocoolers on each cryostat (BT5,BT3)
    - 1Wx2 @4K
    - 44Wx2 @40K
- Achievable temperature
  - Pion capture solenoid : 3.7K
  - Transport solenoids : 4.2K-4.5K(BT3), 4.5K-5.8K(BT5)



# Expected muon yields

- Assuming 400MeVx1μA proton beam
- Quite high intensity  $\mu^+/\mu^-$  can be achieved
- $8 \times 10^8 \mu^+/\text{sec}$
- $2 \times 10^8 \mu^-/\text{sec}$





# Comparison on the pion capture systems


	MuSIC	COMET	NuFact <sup>(1)</sup>
Muon Intensity	$10^8/\text{sec}$	$10^{11}/\text{sec}$	$10^{12-13}/\text{sec}$
Muon Momentum	20-70 MeV/c (Backward)	20-70 MeV/c (Backward)	170-500 MeV/c (Forward)
Time structure	Continuous	Pulsed	Pulsed
Proton Beam Power	400W (0.4GeV)	56kW (8GeV)	4MW (8GeV)
Production Target	Graphite	Tungsten	Mercury jet
Capture Solenoid Max. Field Strength	3.5 T	5.0 T	20 T
Inner radius of Main SC Coil	0.45 m	0.65 m	0.64 m
Outer radius of Main SC Coil	1.0 m	1.6 m	1.78 m

(1) Based on The Muon Collider/Neutrino Factory Target System,  
H.Kirk and K.McDonald (Aug.14,2010) and Study-II report

# Pion Capture System in MuSIC, COMET, and NuFact



**Neutrino Factory**



MuSIC aims to provide the world intense DC muon beam with the 400W proton beam.