

# ECal and Beam Test Update

Michael Nycz

On Behalf of the SoLID Working Group


# Outline

---

- ECal Beam test (2022-2023)
  - Overview
  - Highlights
  - Recent updated - shower gain shift bench testing
    - Michael Lowry (UVa) and Carl Zorn (Jlab)
    - Yanan Liu and Shulong Ji (Shandong University)
- ECal preparation for upcoming Tracking beam test
- Ongoing and Future work

# 2022– 2023 Ecal Beam Test

- Goals - Performance of Ecal in high-rate environment
- Three phases
  - Phase 1 – detector commissioning (82°)
  - Phase 2 – High rate 1 (7°)
  - Phase 3 – High rate 2 (18°)



# Comparison of high-rate (18°) conditions to SoLID

(18°) setting

Run	Target	Thickness (g/cm <sup>2</sup> )	$I_{\text{beam}}$ (μA)	Luminosity (cm <sup>-2</sup> s <sup>-1</sup> )
prod.	LH <sub>2</sub>	0.71	10	$2.7 \times 10^{37}$
prod.	LD <sub>2</sub>	1.69	10	$3.2 \times 10^{37}$
Luminosity scan	LD <sub>2</sub>	1.69	15- 70	$(4.8 - 22) \times 10^{37}$
	carbon	0.574	15- 70	$(0.3 - 1.3) \times 10^{37}$
	aluminum	0.476	15- 70	$(1.0 - 4.6) \times 10^{36}$

SoLID

Experiment	Target	$I_{\text{beam}}$ (μA)	Luminosity (cm <sup>-2</sup> s <sup>-1</sup> )	Rates (kHz)
SIDIS (n)	40-cm ${}^3\vec{\text{He}}$	15	$1.0 \times 10^{36}$	100
SIDIS (p)	3-cm $\vec{\text{NH}}_3$	0.1	$1.0 \times 10^{35}$	10
$J/\psi$	15-cm LH <sub>2</sub>	3	$1.2 \times 10^{37}$	30
PVDIS (d)	40-cm LD <sub>2</sub>	050	$8.0 \times 10^{38}$	15 × 30
PVDIS (p)	40-cm LH <sub>2</sub>	50	$6.7 \times 10^{38}$	15 × 30


# 2022– 2023 ECal Beam Test

- Detector performance
  - LASPD photon PID
  - ECal PID – charged pion rejection
  - Shower non-linearity (Michael Lowry)
- Simulation benchmarking (Ye Tian, Zhiwen Zhao)
- Machine-Learning based PID (Darren Upton, Mohhamed Rafi)


Data and Simulation Comparison

Detector	$e^-$	$\pi^-$	$\pi^+$	$\pi^0$	EM	total	data
SC-A	8.66e-5	0.35	0.22	0.068	869	870	720
SC-D	1.35e-4	0.41	0.26	0.16	258	259	197
PreSh	8.2e-5	0.26	0.16	0.23	20.3	21.0	17.9
Shower	7.1e-5	0.21	0.13	0.2	0	0.54	0.45
SC-B	1.11e-5	0.079	0.038	0.029	702	702	175

Classifier Confusion Matrix




# Detector Performance





Cherenkov NPE  $\sim \frac{1}{2}$  expected from simulation  
(Mirror reflectivity test)


# Detector Performance







LASPD meet SoLID's requirements for photon rejection



# Detector Performance




Confidence that the ECal can provide the PID performance required by all of the SoLID program




# Shower PMT Gain Shift

- MIP signals monitored throughout test for detectors
  - Scin A (B,C,D), LASPD, Preshower, and Shower



# Shower PMT Gain Shift


- MIP signals monitored throughout test for detectors
  - Scin A (B,C,D), LASPD, Preshower, and Shower
- Observed an increase in MIP position of shower models
  - Most dramatic in Shower Top & Left
- Shower Top and Left
  - factor 2 gain increase
- Shower Right
  - ~25% gain increase



Plot courtesy of Ye Tian


# Shower PMT Anode current

Shower\_t BCM vs Anode Current




- Anode currents extracted using FADC signals before event

Shower\_l BCM vs Anode Current




Anode current non-linear in the region of 45-50  $\mu$ A

Shower\_r BCM vs Anode Current



# 2025 Bench Test - JLab


- Reproduce shower behavior during high-rate detector test
- Carl Zorn's PMT setup to mimic beam test
  - **Signal** - LED constant 1 kHz
  - **Background** - LED varied (MHz)
- Same HV as during beam test
- No DAQ setup
  - Exported series of samples from oscilloscope for offline analysis
- Similar bench test preformed by Shandong group with different bases
- Left PMT likely damaged during initial set-up & testing



Tests performed by Michael Lowry (Uva)

# 2025 Bench Test - JLab

- Signal characteristics kept consistent among different PMTs
  - Peak height: 25 mV
  - Peak width: 30 ns (FWHM)



# 2025 Bench Test - JLab

- Signal characteristics kept consistent among different PMTs
  - Peak height: 25 mV
  - Peak width: 30 ns (FWHM)
- Signal LED kept constant, background increased


## Top PMT

Signal Rate [kHz]	Background LED Current [ $\mu$ A]
1.0	0.00
1.0	24.98
1.0	50.03
1.0	99.98
1.0	149.90
1.0	174.82
1.0	199.95
1.0	250.13
1.0	275.13

# 2025 Bench Test - JLab



- Signal characteristics kept consistent among different PMTs
  - Peak height: 25 mV
  - Peak width: 30 ns (FWHM)
- Signal LED kept constant, background increased
- Each setting – measured/stored baseline and peak height

Top PMT



Signal Rate [kHz]	Background LED Current [ $\mu$ A]
1.0	0.00
1.0	24.98
1.0	50.03
1.0	99.98
1.0	149.90
1.0	174.82
1.0	199.95
1.0	250.13
1.0	275.13


# 2025 Bench Test – Jlab: Results



Right PMT appeared to become non-linear earlier than in beam test


# Shandong University PMT Bench Test

- PMT and HV divider : cr-284 from Zhihong Ye(ThU)
  - active base: negative-HV
  - two PMT: ID5785\ID5804
  - Test range:for continuous light from about -1mV - -10mV




Slide Courtesy Yanan Liu and Shulong Ji

# Shandong University PMT Bench Test



5785



5804

## Conclusion

1. The gain of the anode current remains basically unchanged within 20  $\mu\text{A}$
2. 20 - 200  $\mu\text{A}$  gain increase is linear


Figures Courtesy Yanan Liu and Shulong Ji

# ECal preparation for upcoming beam test



# 2026 Tracker Beam Test Preparation

- ECal super-module (7 modules) in place of 3 module shower
  - Different PMT bases than 3 module
- ECal super-module requires new support on existing table
  - Designed by Hall C engineering
  - Flexible to use for 3 module (back-up)
  - Can be used for fiducialization

**See Eric Fuchey's talk for more details**




# ECal Super Module



Images courtesy of Zhihong Ye

# 3 Module Backup

- 3 module shower needed to be considered due to delay in ECal shipment
  - **Before recent decision to delay installation**
  - Preparation to reuse the 3-module set-up
- Super-module support
  - Flexible to use for 3 module ✓



# 3 Module Backup

- 3 module shower needed to be considered due to delay in ECal shipment
  - **Before recent decision to delay installation**
  - Preparation to reuse the 3-module set-up
- Super-module support
  - Flexible to use for 3 module ✓
- New trackers before ECal
  - Cover previous screws which attached plate to table
  - 3 modules moved back – 2 new holes added on table ✓



# 3 Module Backup


- 3 module shower needed to be considered due to delay in ECal shipment
  - **Before recent decision to delay installation**
  - Preparation to reuse the 3-module set-up
- Super-module support
  - Flexible to use for 3 module ✓
- New trackers before ECal
  - Cover previous screws which attached plate to table
  - 3 modules moved back – 2 new holes added on table ✓
- Replace Left shower PMT damaged during bench test
  - Have 1 spare that needs tested ✓
  - Spare PMTs purchased - 5x R11102 ✓
  - 3x bases (for R11102) ✓

# 3 Module Backup

- 3 module shower needed to be considered due to delay in ECal shipment
  - **Before recent decision to delay installation**
  - Preparation to reuse the 3 module set-up
- Super-module support
- **Plan remains to use super-module**
- **Modification are minimal and will only serve as a back-up**
  - Cover previous screws which attached plate to table
  - 3 modules moved back – 2 new holes added on table ✓
- Replace Left shower PMT damaged during bench test
  - Have 1 spare that needs tested ✓
  - Spare PMTs purchased ✓


# Things to do

- Prepare/Test super-module after shipment
  - Test PMTs
  - Can preform similar LED bench test as was preformed by Tsinghua group
  - Carl Zorn's dark box set-up
- 5 preshower tiles & WLS fibers also in shipment
  - Test MAPMTs with preshower
- Test spare PMT to replace Left PMT (3 module)
- Modify/update ECal replay
- Design plan for commissioning of ECal



# Remaining (pre)R&D Activities

## ECal Update (Xiaochao Zheng): SoLID Collaboration Meeting (July 7-8 2025)

- For SoLID ECal, we still need (pre)R&D on:
    - MAPMT readout of Preshower (unless we decide on using regular PMTs – much safer but higher cost)
    - MCP-PMT readout of LASPD
    - PMT active base design and testing → R&D
  - 5 Preshower tiles also included in shipment with super module
    - Good opportunity to test MAPMTs with Preshower
  - 5 Shower PMTs and 3 bases purchased – spares
    - Will work with Electronics group on base
- 
- A diagram consisting of two curved arrows. A red arrow starts from the 'MAPMT readout of Preshower' item and points to the '5 Preshower tiles' item. A blue arrow starts from the 'PMT active base design and testing' item and points to the '5 Shower PMTs and 3 bases purchased' item.

# Summary

---

- The 2022-2023 beam test analysis is (nearly) complete
  - ML PID nearing completion with the recent help of the simulation group
- Completed shower PMT bench test to confirm gain shift observed during the beam test
  - Companion bench test performed by Shandong University group provides input for future base design
  - Shandong University will repeat study using a high-rate pulsed LED
- Preparation is ongoing for the upcoming beam test



# 2026 Tracker Beam Test Preparation


- Will use a 7 module ECal (super module)
  - Being shipped from China
- Delay in shipping-Modify to begin with 3 module during commissioning
  - Update position on table
  - new screws to secure to table and support
  - Replace Left PMT
- With installation delay
  - 7 module ECal will arrive early to mid march
  - Needs to be tested
- 5 preshower tiles also included in
  - May be a good idea to test MAPMTs with preshower

# 2022-2023 Summary




- Completed a high-rate Ecal test
- Completed
  - detector performance
  - PID analyses
  - Nearly completed ML PID analysis
  - Bench test
- Machine Learning PID near competition
  - Requires additional statistics from simulation
- Beam test summary available

# Charged pion rejection



- With open geometry (no magnet)
  - Can only preform charged pion rejection
- Used traditional PID
  - Cherenkov Sum  $\sim 0$
- Apply a "slope" cut in PSh vs. Sh
  - Calculate pion rejection
- Compare with simulation
  - Perform same analysis using Simulation
  - (i.e. trigger, NPE, Scintillator cut)
- Additional studies performed
  - "Offline" to reduce background
  - Machine learning – near completion



- Pion rejection at low current consist
- An offline analysis helped to reduce background



# Charged pion rejection



# 2022– 2023 Ecal Beam Test

- Goal - Performance of Ecal in high-rate environment

