
Mini-Phase Procedure (Darklight)

Document Number: FEL-PR-08-001

Revision Number: Rev. 5, July 10, 2012 (*B. Legg/C. Tennant*)

Technical Custodian: R. Legg

Estimated Time to Perform: 30 minutes

Procedure Overview

A Miniphase of the FEL is required after an overnight shutdown or following a Controlled Access. The Miniphase may also be necessary for machine recovery after degradation due to slow drifts. The Miniphase sets the injector phases, sets the proper charge, phases the linac, optimizes the wiggler and adjusts the pathlength. The procedure is comprised of:

- Section 1.0 Verify the Correct Allsave Has Been Loaded
- Section 2.0 Set the Charge to 60 pC
- Section 3.0 Set the Relative Phase of the Drive Laser and Buncher
- Section 4.0 Gang Phase the Laser-Buncher
- Section 5.0 Set the Phase of Cavity 1-3
- Section 6.0 Gang Phase the Linac
- Section 7.0 Optimize the Energy
- Section 8.0 Adjust the PathLength
- Section 9.0 Appendix I - Required EPICS/MEDM screens

Prerequisites

1. The FEL Startup Procedure has been completed to the point the Miniphase Procedure is referenced and directed to be performed.

Procedure Steps

1.1 Verify the Correct All-Save Has Been Loaded

1. Load an appropriate All-Save. Unless specifically instructed otherwise (FLOG or FEL Shift Plan) this should be either:
 - a. The “morning miniphase” (if setting up from the previous day), or
 - b. The current running setup or what should have been running for access recovery or performance recovery.

NOTE: The point is to start with an intelligent All-Save.

2. Verify that all BLMs are unmasked.
3. Verify the DLPC is configured to produce tune-up beam.

NOTE: Tune-up beam is defined here as:

- Pulsed mode at 2 Hz

- 250 μ s macropulse
 - 4.6 MHz micropulse frequency
- Confirm that tune-up beam exists with acceptable ghost pulses:
 - Inspect the drive laser Tekscope before opening the operator shutter.
 - Any of the SLMs can also be observed when the operator shutter is opened.
 - Is the machine in an acceptable tune-up mode at this point?

A. NO Stop and contact expert assistance **YES** Continue
 - Mask all BLMs, but **only** if the machine is in a tune-up mode and reasonably clean.
 - Open the Miniphase Combo screen (FEL Main Menu \Rightarrow Development \Rightarrow Miniphase Combo).




Figure 1-1: Screenshot of the Miniphase Combo screen.

2.0 Set the Charge to 60 pC

- Set the charge to 60 pC as follows:
 - Adjust the drive laser polarizer (labeled "A" on Figure 1-1) to excite the Unser monitor as observed on Tekscope B (green trace, channel 4) to 140 mV. Is there sufficient charge as measured on Tekscope B?

A. NO Stop and contact expert assistance **YES** Continue

3.0 Set the Relative Phase of the Drive Laser and Buncher

- Open the RF Injector Phase Monitor screen (FEL Main Menu \Rightarrow RF \Rightarrow Injector Phase Monitor).
- B Volts** for **Qtr Cryo 4** should read 0.2280. If it does not, change the gradient in zone 1 cavity 4 by steps of 0.01 MV/m until it does (labeled "B" on Figure 1-1). **NOTE:** it takes several seconds for the value to update.




Figure 3-1: Screenshot of the RF Injector Phase Monitor.

3. Check the *Beam Viewer Timing System* (FEL Main Menu⇒Viewer⇒Beamviewer Timing System) for proper configuration. The **Timing Output** button must be in the **On** position for the Beamanizer application.
4. Map viewer **ITV0F06** to Monitor 17.
5. While monitoring the Beamanizer image of **ITV0F06**, adjust the drive laser phase (labeled “C” on Figure 1-1) to restore the beam to the standard **ITV0F06** image (see Figure 3-2).

NOTE: To load the standard image click “Off-line” on the Beamanizer and navigate to C:\Documents and Settings\fella\Desktop\Beam Images\Mini phase images and select the **ITV0F06_consolidated_beam** image (the file must have the .pnm extension).




Figure 3-2: ITV0F06 as viewed with the Beamanizer.

- Remove ITV0F06.

4.0 Gang Phase the Laser-Buncher

CAUTION: Do not use the laser-buncher gang phase for adjustment in this section.

- Insert **ITV0F04**.
- Map **ITV0F04** to Monitor 17 using the video switcher controls.
- Take the Beamanizer Off-line and load the proper **ITV0F04** file. The file must have the .pnm extension. Files are located at C:\Documents and Settings\fella\Desktop\Beam Images\Mini phase images. File name is ITV0F04_consolidated_beam.
- Use the bars to frame the Off-line image.
- Take the Beamanizer on-line. The present condition of the beam at **ITV0F04** will be displayed (see Figure 4-1).




Figure 4-1: ITV0F04 as viewed with the Beamanizer.

- Adjust the laser phase and buncher phases in 1° increments, remembering to adjust the laser phase 1° for every degree of buncher adjustment (labeled "D" on Figure 1-1). The goal is to adjust the phases such that the spot approximately matches the preloaded shape boundaries.
- Take the Beamanizer off-line.
- Withdraw **ITV0F04**.

5.0 Set the Phase of Cavity 1-3

- Insert **ITV0F06**.
- Map **ITV0F06** to Monitor 17 using the video switcher controls.
- Take the Beamanizer Off-line and load the proper **ITV0F06** file. The file must have

the .pnm extension. Files are located at C:\Documents and Settings\fella\Desktop\Beam Images\Mini phase images. The appropriate file to use will be specified in the Shift Plan.

4. Use the bars to frame the off-line image.
5. Take the Beamanizer on-line. The present condition of the beam at **ITV0F06** will be displayed (see Figure 3-2).
6. Does the beam image match the preloaded image?
 - A. **NO** Set the increment on Cavity 1-3 phase slider to 0.1° (labeled “E” on Figure 1-1) and adjust to match the preloaded image. The goal is to adjust the phase so that the spot approximately matches the preloaded shape boundaries **YES** Continue to Step 7.
 - C. If desired, save the beam image.
 - D. Take the Beamanizer Off-line.
 - E. Withdraw **ITV0F06**.
7. Section 3.0, Section 4.0 and Section 5.0 should be repeated after the completion of Section 5.0 to ensure the symmetry of the drive laser phase is maintained. This may involve an iterative process to achieve an acceptable solution to the three sections.

CAUTION: If Cavity 1-3 is changed by more than 0.5° , this section should be repeated because the zero-crossing will be lost.

 - a. Has the symmetry of the drive laser phase been verified per Section 3.0 and an acceptable solution reached for Sections 3.0, 4.0 and 5.0?
 - A. **NO** Go to Section 3.0, Set the Relative Phase of the Drive Laser and Buncher and check Sections 3.0, 4.0 and 5.0 to ensure the drive laser phase symmetry is maintained and injector phases are satisfactory **YES** Continue
8. Zero the RF Phase Monitor Relatives by pressing the **Zero All Relatives** on *Injector RF Phase Monitor* and add a screen shot of the EPICS screen to the FLOG entry of the Miniphase.

6.0 Gang Phase the Linac

NOTE: The average of the relative horizontal positions at **IPM2F07** and **IPM2F09** will be used as an indication of proper phasing. These two BPMs are at dispersive locations. The average of the two relative horizontal positions is an indication of the machine energy.

1. Decrease the gang phase by 20° in Zone 2 (labeled “F” on Figure 1-1).
2. Note the change of the average BPM signal on the striptool. Did the average signal change by less than 0.5 mm?
 - A. **NO** the XREL average changes more than 0.5 mm as the gang phase is changed by 20° , the module is not properly phased. The relationship between gang phases and linac energy gain is shown below in Figure 6-1. Follow the steps below to phase the module:
 - If the XREL average drops when the gang phase is changed by 20° , the gang phase is too negative. Add the 20° back and increase the gang phase by a few tenths of a degree. Go back to Step 1 and repeat the measurement.

- If the XREL average increases when the gang phase is changed by 20° , the gang phase is too positive. Add the 20° back and decrease the gang phase by a few tenths of a degree. Go back to Step 1 and repeat the measurement.




Figure 6-1: Relationships of gang phase, beam position, and energy.

3. Restore the gang phase by adding 20° back
4. Increase the gang phase by 30° in Zone 3 in 15 degree steps.
5. Note the change of the average BPM signal on the striptool. Did the average signal change by less than 0.5 mm?
 - A. NO** the XREL average changes more than 0.5 mm as the gang phase is changed by 30° , the module is not properly phased. The relationship between gang phases and linac energy gain is shown below in Figure 6-1. Follow the steps below to phase the module:
6. If the XREL average drops when the gang phase is increased by 30° , the gang phase is too positive. Subtract the 30° back out and decrease the gang phase by a few tenths of a degree. Go back to Step 4 and repeat the measurement.
7. If the XREL average increases when the gang phase is increased by 30° , the gang phase is too negative. Subtract the 30° back out and increase the gang phase by a few tenths of a degree. Go back to Step 4 and repeat the measurement.
8. Go back to Step 6.1 and repeat Steps 1 through 3 for Zone 4. The three rf zones are now properly phased.
4. Go to Section 7.0, Optimize the Energy after the three zones are properly phased.

7.0 Optimize the Energy

1. Insert viewer **ITV4F03**. This is the viewer used with the Happek device.
2. Add 30 degrees to the gang phase of Zone 3. The spot at SLM2F08 should go from a Spot to a Horizontal bar indicating the linac is no longer cross-phased.
3. Maximize the output of the Golay cell signal amplitude by adjusting the vernier cavity

gradient (labeled “G” on Figure 1-1). A step size of 0.01 MV/m should be used for adjustments. See Figure 7-2 for typical scope display of the Golay cell.

NOTE: The output of the Golay cell, which is used in the Happek device, is always connected to channel 1 of *felscope01*. The screen of the scope is usually shown on Monitor 9 in the control room but can be mapped to any of the monitors via the video distribution system (Bank 12). The signal level should be a few hundred millivolts.





Figure 7-1: Golay signal shown on scope channel 1.

5. Retract the ITV4F03 viewer and switch monitor 17 (the Beamanizer) to SLM5F02. Return the macropulse repetition frequency to 4.68 MHz and macropulse length to 250 usec.
6. Adjust the vernier cavity gradient so that the CSR effect starts to show up at the 5F02 SLM. Typical response is to reduce the energy by ~0.2 MeV when maximizing the Golay signal and then typically a fraction of 0.1 MeV to achieve the correct CSR effect on the 5F02 SLM. Figure 7-2 shows the CSR effect “turned off”, and Figure 7-3 shows the CSR effect beginning to show up. There must be tails on both sides of the bunch beginning to show up as shown in Figure 7-3.

8.



2. Adjust **Current Setpoint** of the Pathlength Box Supply to set the pathlength (labeled



"H" on Figure 1-1). This is accomplished by centering the beam spot vertically on the 1G01 viewer. Adjust the **Current Setpoint** in 0.1 A increments to minimize the vertical beam spot size on the 1G01 viewer.

3. PROCEDURE COMPLETE.

9.0 Appendix I - Required EPICS/EDM screens (these have not been thoroughly checked 9/14/2010 C.T.)s

Useful screens/strip tools/monitors to have open and/or mapped.

- | | |
|---|--|
| 1. drive laser parameters | striptool |
| 2. drive laser Tekscope | scope⇒monitor |
| 3. Drivemaster | FEL Main Menu⇒Drive Laser⇒Advanced Drive Laser
Master Control⇒ <i>Advanced Drive Laser Master Control</i>
scope⇒monitor |
| 4. drive laser autocorrelator | |
| 5. Beamanizer | |
| 6. Tekscope B | scope⇒monitor |
| 7. Dump charge/current monitor | FEL Main Menu⇒Dumps⇒Beam Current/Power⇒ <i>Beam Current</i> |
| 8. "phasetheinjector" | strip tool |
| 9. Injector RF 4-seater | FEL Main Menu⇒RF FEL Main Menu⇒Injector
Ops⇒Ops 4-seater⇒ <i>R4SEATER</i> |
| 10. video switcher | FEL Main Menu⇒Viewer⇒Video Switcher Control⇒ <i>FEL Video Switching System</i> |
| 11. Viewer controls | FEL Main Menu⇒Viewer |
| 12. RF Combo screens for zones 2,3, and 4 | FEL Main Menu⇒RF FEL Main Menu⇒Zone 2 Misc⇒ <i>RF Combo 4L02</i>
FEL Main Menu⇒RF FEL Main Menu⇒Zone 3 Misc⇒ <i>RF Combo 4L03</i>
FEL Main Menu⇒RF FEL Main Menu⇒Zone 4 Misc⇒ <i>RF Combo 4L04</i> |
| 13. BPM combo screens | FEL Main Menu⇒BPM⇒BPM Spikes⇒Combo⇒ <i>BPM Absolute Spikes</i>
FEL Main Menu⇒BPM⇒BPM Spikes⇒Combo⇒ <i>BPM Relative Spikes</i> |
| 14. Happek controls | FEL Main Menu⇒Data Acq⇒Happek⇒IR-
Upstream⇒ <i>FEL Happek Interferometer - IR(Upstream)</i> |
| 15. 4F and 5F corrector controls | FEL Main Menu⇒Magnets⇒Magnet
Commander⇒4F⇒4F Correctors⇒ <i>Correctors for the (4F) Region</i> FEL Main Menu⇒Magnets⇒Magnet
Commander⇒5F⇒5F Correctors⇒ <i>Correctors for the (5F) Region</i> |
| 16. 5F multipole controls | FEL Main Menu⇒Magnets⇒Magnet
Commander⇒5F⇒5F Multipoles⇒ <i>Multipoles for the (5F) Region</i> |
| 17. MPATH control screen | FEL Main Menu⇒Magnets⇒Box Supplies⇒Pathlength
Box Supply⇒ <i>PathLength Power Supply</i> |
| 18. Beam Viewer Timing control screen | FEL Main Menu⇒Viewer⇒Beamviewer Timing
System⇒ <i>Beam View Timing System</i> |