




# Superferric 3T CIC Dipole R&D 2016/17 Project Report




Peter McIntyre

Texas A&M University

# CIC Dipole R&D: 8/2017 – 3/2018

- We are developing a 3 T superferric dipole with cable-in-conduit (CIC) superconductor for its windings.
- \$139K R&D was funded in August 2016.
- Goals of the 2016/17 R&D task:
  - fabricate a long length of CIC cable, incorporating all features required for the CIC dipole.
  - wind a few turns of the CIC cable onto the coil form (fabricated in FY15) and evaluate the coil-winding methods using CIC cable.
  - Develop methods for splice joints and quench protection suitable for use in a 1.2 m model dipole and in 4 m JLEIC dipoles.
- I will report on our success in these goals and our proposal to build a 1.2 m model dipole ready to test by 4/2018.




# 5/20/2016: Mockup winding complete




The culmination of our previous development was fabrication of a 1.2 mockup winding – validating ability to wind CIC and hold tolerances on conductor placement for collider field homogeneity.



# Develop long-length CIC cable



15 NbTi/Cu wires are cabled onto a perforated spring tube.




The cable is inserted in a sheath tube, and the sheath is drawn onto the cable to just compress the wires against the spring tube.





# Path to long-length CIC cable

## 1. Perforated center tube (316L SS):

- Punch pattern of holes in 316L SS foil strip:
- Roll/weld strip to form tube:
- Initial problems with weld puckers:



✓ Problem solved:




## 2. Draw perforated tube to final OD, removes weld bulge.

- ✓ Installed/commissioned  
12 m drawbench
- ✓ Drew perf. tube to final size  
(4.762 mm)
- ✓ Confirm roundness,  
dia. tolerance to  $\pm.02\text{mm}$




## 3. Fabricate CIC cable using perf. center tube, NbTi wire, CuNi sheath

- ✓ Form U-bend with 5 cm radius.
- ✓ Remove sheath and wires, examine weld, roundness of perf. tube:





#### 4. Fabricate long-length CIC cable on perf. center tube:




- Developed a custom cabler that integrates on drawbench, maintains constant tension and twist pitch.
- ✓ Completed 12 m cable.
- Extensible to 125 m inside USB.
- Option to cable at NEEW.



## 5. Long-length sheath tube


- Original choice for sheath: seamless Monel 400
  - Ordered from Shanghai Phoenix Alloy
  - They made bad billet (composition or heat treat)
  - Tube broke repeatedly in drawing
- Equally good alternative: seamless CuNi alloy 70600
  - ✓ Ordered from Small Tube Products, Delivered last week.
  - ✓ Excellent uniformity, high-strength
  - ✓ Weld/solder compatibility for splice joints
- Third option: continuous tube forming
  - HyperTech has developed CTFF to form sheath tube directly onto cable with SS foil overwrap.
  - Funded from SBIR Phase 1, successful
  - Phase 2 award notified, now on hold...
  - ✓ Demonstrated He leak-tight
  - ✓ Demonstrated no damage to wires in cable.



# Continuous forming/welding of sheath tube on CIC cable - CTFF



Strip Payoff



Multi-wire or tape Payoff



Forming rolls



Closing Rolls



Laser Welding



Roll Reducing



Straight Drawing




Tube Take-up



Operator Panel



Example of Welded Multifilament Wire could be stacked YBCO Tape



Hyper Tech has adapted its continuous-tube-forming process to form and laser-weld sheath tube on CIC cable (SBIR Phase 1). They can prepare km-length CIC cables with no length constraints.

- ✓ Validated that CTFF can weld Monel tube onto NbTi cable, no damage.
- ✓ Developed the weld process to produce He-tight seam – passed cold-shock pressure tests with He to 600 psig.



## 6. First medium-length CIC cable completed:




- ✓ We have options for fabrication of long-length CIC cable:
- Cable NbTi wire and SS overwrap on perf tube @ USB, or @ NEEW.
  - Pull cable into seamless sheath @ USB, or form CTFF @ HyperTech
  - Draw cable to compact CIC @USB, or at Luvata.



# We have succeeded in fabricating long-length CIC cable entirely in-house


1.-Straighten the inner tube by using draw bench to pull perforated tube into straightener.



2.-Cabling 15 Al-Bronze 1.2mm OD wires around the 3/16" perforated tube with a 3" twist pitch.



2.1) Twist pitch maximum and minimum respectively –Pretty consistent




3.-0.001" Stainless Steel foil wrapped around without overlap. Secure at both ends with superglue.






4.-Straighten outer tube same procedure as #1 -Spool custom built-



5.-Insertion of "core" into outer tube by sliding into it




6.- Swaging tip of CIC with a .300" OD swage die






7.- Drawing process, using DSW-20 lube and .3475" Drawing die for the first run and a .320" for the final sizing.




9.- Spooling it in a 30.5" radius spool.




## 7. Form U-bends in CIC using the motorized tooling that was developed for the mockup winding.

- The tooling was developed to bend empty CuNi tube to the 5 cm radius required for the CIC end windings.
- The CIC cable is much stiffer than the empty tube.
- Form bends to determine whether the forming dies work correctly to bend CIC.
- Requires more overbend to overcome spring-back – must modify forming dies.
- ✓ Formed U-bends are intact inside, no problems.



8. Splice joint should be robust, low-resistance, easily made/unmade



**Calculated joint resistance 0.1 n $\Omega$**   
**Naturally provides for He flow manifold.**



# We propose a 2-year scope of work and budget to build and test a 1.2 m 3 T model dipole.

- FY2018: \$500K
    - 125 m cable lengths
    - FRP structure
    - Fabricate windings
- |             |               |                 |                    |                 |                   |
|-------------|---------------|-----------------|--------------------|-----------------|-------------------|
| Flux return | FRP structure | 125 m CIC cable | Fabricate windings | Instrumentation | Warm measurements |
|-------------|---------------|-----------------|--------------------|-----------------|-------------------|
- Precision metrology of windings on structure
  - Instrumentation:
    - Quench heaters
    - Voltage taps
    - Splice joints and leads
  - Flux return structure
  - Assemble and preload

- Fiscal 2019

\$400K + BNL expense


- Warm measurements of harmonics, comparison with metrology and simulations
- Evaluate shim strategy to cancel multipoles
- Evaluate effects of preload strategy on harmonics
- Final assembly and checkout
- Cool-down
- Cold testing of the dipole
- Multipole measurements
- Ramp rate studies
- Provisions for several rounds of warm-up/cool-down



# Current Status of CIC dipole development

- ✓ Fabricated and tested short segments of CIC cable in its final form.
- ✓ Bent the CIC cable in the configuration required for the windings of the dipole. We have verified the short-sample current in extracted strands.
- ✓ A 1.2 m model dipole requires a single 125 m CIC cable. A 4 m dipole requires two 125 m CIC cable segments.
- ✓ Fabricated perforated center tubes and drawn to final size.
- ✓ Successfully cabled medium-length cable @ USB.
- ✓ Successfully pulled medium-length cable into sheath, drawn to final compaction.
- ✓ Validated that we can form medium-length CIC cable in U-bend for end windings, cable is fine inside.
- ✓ Developed and validated CTFF forming of sheath onto CIC

# EIC Review Panel challenged us to consider option of Energy Doubler



**We significantly improved our earlier 6 T CIC design by grading the conductor.**

| Design field $B_0$ | 3 T               | 6 T                | 6T graded          |
|--------------------|-------------------|--------------------|--------------------|
| Coil current       | 13.7 kA           | 17.2 kA            | 18.6               |
| Coil field @ $B_0$ | 3.5 T             | 6.9 T              | 7.1                |
| Bore field @ SS    | 3.8 T             | 6.2 T              | 6.4                |
| # turns in coil    | 24                | 54                 | 54                 |
| Cable:             |                   |                    |                    |
| # strands          | 15                | 14                 | 18/10              |
| strand dia.        | 1.2 mm            | 1.5 mm             | 1.39 mm            |
| total s.c. area    | 8 cm <sup>2</sup> | 27 cm <sup>2</sup> | 23 cm <sup>2</sup> |
| Flux return size   | 20 cm             | 33 cm              | 35 cm              |


Magnet cost for a CIC dipole is proportional to # turns, flux return size.

On that basis, 6 T dipoles would cost  $\sim 2.25$  x cost of 3 T.

Compare to  $\cos \theta$ , for which cost  $\sim B^2$ .



6 T coil structure is same as for 3 T CIC dipole, but 5 layers instead of 3 layers




Half-winding of a 4 m dipole =  
27 turns  
~ 540 m CIC cable length


Priority on completing the  
development of continuous  
tube—forming fabrication of  
sheath tube directly onto cable

**Building/testing a 3 T model dipole would go far toward validating the 6 T cousin.**



# End region is bigger but workable



# 6 T CIC dipole design parameters




|                 |                  |
|-----------------|------------------|
| <b>dstrand</b>  | <b>1.39 mm</b>   |
| <b>Nstrands</b> | <b>18/10</b>     |
| <b>Cu/Sc</b>    | <b>1.2</b>       |
|                 | <b>9.94/6.8</b>  |
| <b>Dcable</b>   | <b>8 mm</b>      |
| <b>Bssl</b>     | <b>6.39 T</b>    |
| <b>Bcab</b>     | <b>7.14 T</b>    |
| <b>Issl</b>     | <b>19800 A</b>   |
| <b>Estored</b>  | <b>216 kJ/m</b>  |
| <b>L</b>        | <b>1.10 mH/m</b> |





# The CIC block-coil dipole is amp-efficient.



# Value engineering

2014: Design a superconducting dipole to optimize cost/performance for JLEIC requirements.

| Element Description  | Unit Measure | # Units | Unit Cost | Cost Basis | Total Mat'l Cost \$ | Hrs/Unit | Total Hrs  | Total Labor \$ | Total Mat'l + Labor \$ | Tooling        | Engineering, QC & Supervision |
|--|--------------|---------|-----------|------------|---------------------|----------|------------|----------------|------------------------|----------------|-------------------------------|
| <b>Beam Tube, Coil Collar, End Block &amp; Flared Ends</b>       |              |         |           |            |                     |          |            |                |                        |                |                               |
| Cold Bore Tube - Cu Plated                                       | EA           | 1       | 2,421     | Bailey     | 2,421               | 3        | 3          | 237            | 2,658                  | 5,000          | 150                           |
| Beam Tube Flange   | EA           | 2       | 200       | ISC        | 400                 | 4        | 8          | 632            | 1,032                  |                | 100                           |
| Coil Body Form - injection-molded fiber-reinforced Kel-F         | EA           | 1       | 3,600     | ISC        | 3,600               | 6        | 6          | 474            | 4,074                  | 15,000         | 150                           |
| Flared End Form -injection-molded fiber-reinforced Kel-F         | EA           | 2       | 300       | Rebling    | 600                 | 6        | 12         | 948            | 1,548                  | 5,000          | 40                            |
| Assemble Coil Form on Beam Tube - body and flared ends           | Assy         | 1       |           |            | -                   | 28       | 28         | 2,212          | 2,212                  | 10,000         | 300                           |
| <b>Coil Assembly</b>   |              |         |           |            |                     |          |            |                |                        |                |                               |
| NbTi strand, 0.8 mm dia, 50% Cu                                  | km           | 5.4     | 485       | Luvata     | 2,619               |          | -          | -              | 2,619                  |                | 500                           |
| Cabling and insulation of NbTi conductor                         | EA           | 1       | 1,454     | NEEW       | 1,454               |          | -          | -              | 1,454                  |                | 750                           |
| Coil Winding   | EA           | 1       |           | Bailey     | -                   | 40       | 40         | 3,160          | 3,160                  | 50,000         | 640                           |
| Install insulating shell, sizing and impreg curing               | Assy         | 1       | 1,200     | Rebling    | 1,200               | 16       | 16         | 1,264          | 2,464                  | 20,000         | 320                           |
| Splice Preparation & Fab   | EA           | 2       | 50        |            | 100                 | 3        | 6          | 474            | 574                    | 1,000          | 250                           |
| Quench Protection Heaters  | EA           | 4       | 30        |            | 120                 | 2        | 7          | 553            | 673                    | 2,000          | 500                           |
| Voltage Taps   | Assy         | 1       | 50        |            | 50                  | 2        | 2          | 158            | 208                    | 2,000          | 300                           |
| Temp Sensors   | EA           | 2       | 50        |            | 100                 | 1        | 2          | 158            | 258                    |                | 200                           |
| <b>Total cost of coil/beam tube assembly</b>                     |              |         |           |            | <b>12,664</b>       |          | <b>130</b> |                | <b>22,934</b>          | <b>110,000</b> | <b>4,200</b>                  |
| <b>Flux Return</b>   |              |         |           |            |                     |          |            |                |                        |                |                               |
| Flux Return, Lamination Material                                 | EA           | 1380    | 2         | CERN       | 2,567               |          | -          | -              | 2,567                  |                | 600                           |
| Flux Return, Lamination Stamping                                 | EA           | 1380    | 5         | Bailey     | 7,397               |          | -          | -              | 7,397                  | 40,000         | 1,280                         |
| Lamination Pack Shuffling, Stacking, Compression, Weld           | Assy         | 16      |           |            | 200                 | 3        | 40         | 3,160          | 3,360                  | 15,000         | 640                           |
| He Vessel Clamshells, 304 SS                                     | EA           | 2       | 3,144     | Bailey     | 6,288               |          | 10         | 790            | 7,078                  | 5,000          | 640                           |
| He Vessel End Housings, 304 SS                                   | EA           | 2       | 500       | Bailey     | 1,000               |          |            |                | 1,000                  | 5,000          | 400                           |
| <b>Total Cost of Flux Return/He vessel subassemblies</b>         |              |         |           |            | <b>17,452</b>       |          | <b>50</b>  |                | <b>21,402</b>          | <b>65,000</b>  | <b>3,560</b>                  |
| <b>Cold Mass Assembly</b>  |              |         |           |            |                     |          |            |                |                        |                |                               |
| Assemble Coil Assembly, Flux Return Halves, He Vessel Clamshells | Assy         | 1       |           |            | -                   |          | 24         | 1,896          | 1,896                  | 25,000         | 400                           |
| Preload Cold Mass, Electrical & Alignment QC                     | Assy         | 1       | 200       |            | 200                 |          | 32         | 2,528          | 2,728                  | 15,000         | 240                           |
| Warm magnetic measurements                                       |              |         |           |            |                     |          |            |                |                        |                |                               |
| Assemble End Housings on Cold Mass, Beam Tube, Weld & Checks     | Assy         | 1       | 200       |            | 200                 |          | 24         | 1,896          | 2,096                  | 8,000          | 320                           |
| Shipping & handling  |              | 1       | 3,000     |            | 3,000               |          | 6          | 474            | 3,474                  |                |                               |
| Cold testing   |              | 1       | 6,000     |            | 6,000               |          | 20         | 1,580          | 7,580                  | 100,000        | 2,000                         |
| <b>Total manufactured cost of dipole cold mass</b>               |              |         |           |            | <b>39,515</b>       |          | <b>286</b> |                | <b>62,109</b>          | <b>323,000</b> | <b>10,720</b>                 |

Develop a cost model, based on previous history of s.c. dipoles (SSC, RHIC, HERA, LCH, SIS100) to guide the optimization. *Predict ~\$100K per 4 m dipole cold mass.*

# 2016: Develop production tooling, build mock-up winding, measure cable positions

Using what we now know, we made a revised cost projection using actual labor, actual tooling, actual materials and fabrication contracts.

*Estimate \$155K/dipole for first cold masses.*



**Consistent with first estimates!**

Based upon our experience to date, I am confident that we should be able to build the arc dipoles and quadrupoles for approximately the budget that we estimated two years ago when we began.

| CIC cable                                      |  | quantity for 4 m dipole | single-magnet cost |
|--|--|-------------------------|--------------------|
| NbTi wire                                      |  | 3600 m                  | 14,400             |
| Monel Sheath tube                              |  | 240 m                   | 2,286              |
| perforated center tube                         |  | 240 m                   | 960                |
| SS tape overwrap                               |  | 480 m                   | 1,440              |
| cabling  |  |                         | 5,000              |
| pulling cable into sheath                      |  | 72 FTE hrs              | 3,600              |
| drawing sheath to final size                   |  | 48 FTE hrs              | 2,400              |
|  |  |                         | <u>30,086</u>      |
| <b>beam tube &amp; G11 structural elements</b> |  |                         |                    |
| SS beam tube                                   |  |                         | 4,000              |
| G11 material                                   |  |                         | 6,000              |
| G11 body segments                              |  |                         | 8,000              |
| G11 end elements                               |  |                         | 24,000             |
| Ti rails                                       |  |                         | 6,000              |
| quench heater foils                            |  |                         | 3,000              |
| fab, impreg of beam                            |  | 80 FTE hrs              | 4,000              |
|  |  |                         | <u>55,000</u>      |
| <b>winding the dipole</b>                      |  |                         |                    |
| winding labor                                  |  | 256 FTE hrs             | 12,800             |
| QC, winding completion                         |  | 120 FTE hrs             | 6,000              |
|  |  |                         | <u>18,800</u>      |
| <b>flux return</b>                             |  |                         |                    |
| lamination steel                               |  | 5.12 tons               | 15,360             |
| die-stamping                                   |  | 1600 pieces             | 8,000              |
| clean/stack/weld half-cores                    |  | 80 FTE hrs              | 4,000              |
|  |  |                         | <u>27,360</u>      |
| <b>cold mass assembly</b>                      |  |                         |                    |
| install instrumentation                        |  | 80 FTE hrs              | 4,000              |
| assemble winding assy with I                   |  | 120 FTE hrs             | 6,000              |
| QC, preload                                    |  | 80 FTE hrs              | 4,000              |
| warm measurements                              |  | 60 FTE hrs              | 3,000              |
| shim winding, reassemble                       |  | 80 FTE hrs              | 4,000              |
| weld cold mass                                 |  | 64 FTE hrs              | 3,200              |
|  |  |                         | <u>24,200</u>      |
| <b>total cold mass cost</b>                    |  | <b>1140 FTE hrs</b>     | <b>155,446</b>     |



# SBIRs that benefit our development of the ring dipoles and the IR magnets

- **MAG1:** Phase 2 for development of continuous tube forming of sheath tube onto the cable for long-length CIC cable.
- **MAG4:** Phase 1 for development of CIC cable containing  $\text{Nb}_3\text{Sn}$  and  $\text{MgB}_2$  wires.