



C75 Schedule and Resources Cavity and Cryomodule

Reilly/Davis/Legg/McEwen

Contents

- Updated cost comparison C50/C75/C100
- Schedule and resources for C75-01
 - Based on C50-11 and C50-12
- Infrastructure changes
- High level plan for C75-02
- A preliminary plan for doing two C75 per year
- Quality systems in SRF for cryomodules
- Summary

C50/C75/C100

Update - February 2018, with new vendor quotes for C75 & C100

	# Cav	cells /cav	cav length m	Active Length m	fill factor %	MV	volts /cav (MV)	gradient (MV/m)	klystron power	unit cost (FY18 M\$ Direct)	*RF Cost	Total Cost FY18 Direct	MV (gain)	V(gain) /\$
C50	8	5	0.5	4	48.1	50	6.25	12.5	6	1.42		1.42	20	14.1
C75 [†]	8	5	0.5	4	48.1	75	9.4	18.8 [‡]	8	1.76	0.84	2.60	45	17.3
C100 [‡]	8	7	0.7	5.6	64.4	100	12.5	17.9 [‡]	13	4.57	1.81	6.38	70	11.0

C50 Estimate

- Based on C50-11 + escalation
- Added Mag shielding & NEG Pumps

[†]New cells or new processing required to achieve higher Q's and gradients

^{*}Engineering required at additional cost (not included)

[‡]Digital LLRF required

C75 Estimate

- Based on C50-11 with C75 Cavities
- Includes Actual Vendor Quotes as of June2017 for Cavity Fab, Ingot & Ingot Slicing (reusing end groups)
- Includes Mag shielding & NEG Pumps

C100 Estimate

- Includes updated quotes from Vendors for one Cryomodule as of August 2017 for the following major procurements
 - Nb & Cavities, He Vessel, Tuners, Thermal Shield, Magnetic Shield, Vac Vessels (End cans were not requested).
- All other procurements used escalation + scaling factor (+15%) due to low volume buys
- C75 & C100 - LL RF for C75 & C100 and High power (for C100) based on cost estimate from C. Hovator (June2017)

What is not included

- One time R&D costs for Cavity Development (already done)
- One time cost for LL RF Development to address obsolesce (same design for c50, C75 and/or C100 zones)
- Wave Guide Vendor Development + 8 Wave Guides

Ref. DRAFT C50 vs C75 vs C100 Rev 49- 13Feb2017


Adjusted CPP Schedule

Fiscal Year	Modules Installed during SAD
FY18	F100, SL21
FY19	C75-01
FY20	C75-02, C100-Refurb-0
FY21	C75-03, C75-04, C100-Refurb-1
FY22	C75-05, C75-06, C100-Refurb-2
FY23	C75-07, C75-08, C100-Refurb-3
FY24	C100-Refurb-4
FY25	C75-09
FY26	C100-Refurb-5
FY27	C75-10

CPP Cryomodule Plan


[illegible]

Plan C75-01 and C75-02




Forecasted C75-01 FTE per Month

Fiscal Year	FY18				FY19									
	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul
C75-01														
Cavity Procurement														
Cavity process and qual														
Cryounit Assembly														
Cryomodule assembly														
Acceptance test														
Install and commission														
Total FTE	0.12	0.25	0.5	0.5	0.85	0.85	1.4	1.2	1.2	0.8	0.8	0.6	0.5	




Forecasted C75-01 FTE per Month



C50-11 Actual FTE per Month


FY13/14	Oct '12	Nov '12	Dec '12	Jan '13	Feb '13	Mar '13	Apr '13	May '13	Jun '13	Jul '13	Aug '13	Sep '13	Oct '13
C50-11													
CM Disassembly													
Cavity process and qual													
Cryounit Assembly													
Cryomodule assembly													
Acceptance test													
Install and commission													
Total FTE	0.16	0.16	0	0.31	0.88	1.28	1.52	1.61	1.11	0.86	0.77	0.55	0.1



LCLS II Ramp Down and C75-01


Task Name	Duration	Start	Finish	2018				2019		
				Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3
LCLS II Assembly	315 days	Wed 2/14/18	Tue 4/30/19							
CM15 Assembly Complete	0 days	Wed 10/3/18	Wed 10/3/18					◆ 10/3		
CM16 Assembly Complete	0 days	Wed 10/24/18	Wed 10/24/18					◆ 10/24		
CM17 Assembly Complete	0 days	Wed 11/14/18	Wed 11/14/18					◆ 11/14		
CM18 Assembly Complete	0 days	Wed 1/16/19	Wed 1/16/19					◆ 1/16		
CM19 Assembly Complete	0 days	Thu 2/14/19	Thu 2/14/19					◆ 2/14		
CM20 Assembly Complete	0 days	Thu 3/14/19	Thu 3/14/19					◆ 3/14		
C75-01 CM Assemble and Test	261 days	Mon 6/4/18	Mon 6/3/19							
Cavity Pair Qualification	150 days	Mon 6/4/18	Fri 12/28/18							
Cryounit Assembly	103 days	Mon 10/1/18	Wed 2/20/19							
Cryomodule Assembly	105 days	Mon 12/3/18	Fri 4/26/19							
Acceptance Test	26 days	Mon 4/29/19	Mon 6/3/19							
C75-01 Install and Commissioning	25 days	Tue 6/4/19	Mon 7/8/19							

A Plan for Completing (2) C75 + (1) C100




Forecast FTE per Month at Peak

Fiscal Year	FY20									FY21									
	Feb-20	Mar-20	Apr-20	May-20	Jun-20	Jul-20	Aug-20	Sep-20	Oct-20	Nov-20	Dec-20	Jan-21	Feb-21	Mar-21	Apr-21	May-21	Jun-21	Jul-21	Aug-21
C75-02 Cryomodule																			
C100-01 Cryomodule																			
C75-03 Cryomodule																			
C75-04 Cryomodule																			
C100-02 Cryomodule																			
C75-05 Cryomodule																			
C75-06 Cryomodule																			
C75-02 Cryomodule	0.53																		
C100-01 Cryomodule	1.23	1.23	0.83	0.83	0.63	0.53													
C75-03 Cryomodule	0.12	0.25	0.50	0.50	0.85	0.85	1.40	1.20	1.20	0.80	0.80	0.60	0.50						
C75-04 Cryomodule					0.53	0.53	0.88	0.88	1.43	1.23	1.23	0.83	0.83	0.63	0.53				
C100-02 Cryomodule									0.53	0.53	0.88	0.88	1.43	1.23	1.23	0.83	0.83	0.63	0.53
C75-05 Cryomodule													0.53	0.53	0.88	0.88	1.43	1.23	1.23
C75-06 Cryomodule																	0.53	0.53	0.88
Total FTE per Month	1.89	1.48	1.33	1.33	2.02	1.92	2.28	2.08	3.17	2.57	2.92	2.32	3.30	2.40	2.65	1.72	2.80	2.40	2.65





Infrastructure for C75 Cryomodules

- Space to add a 4th rail for CEBAF modules during LCLS II
- Decision not to add for C75-01
 - Plan to use existing rails similar to C50-13
- Cryo-unit rails will be added for C75-01
- Timing for adding 4th rail will be driven by future work




SRF Organization



Key Points

- Cavities/Cryomodules move through work centers
- Work centers have leads
- Do not have project based dedicated teams
- Work is prioritized scheduled in weekly planning sessions
- Schedule is reviewed daily (twice)

SRF Facilities at JLab



SRF Quality Management System

- Goal to enable high quality, highly effective and efficient operations in fulfilling the SRF Mission.
 - Models the ISO 9001 Quality Standards.
 - Supplements the Jlab lab-wide Quality Assurance Plan.
- Structured deployment of quality assurance practices through quality policy and procedures.
- System is being implemented and continually improved.

Quality Policy: SRF Quality Manual QA-M-001

A “Road Map” describing the SRF Mission, the quality assurance/control systems, and mechanism to produce high quality deliverables.

Highlights:



- a) Process elements are based on **ISO 9001**
- b) Lists a full set of quality process procedures (section 2).
- c) Explains different levels of process documents (section 3).
- d) Supplements lab-wide **Jlab Quality Assurance Plan** (section 3).
- e) Describes SRF **process interactions** (section 4.2.2.1).
- f) Captures SRF **Mission Statement** (section 5.3).
- g) Explains SRF quality objectives (section 5.4.1).
- h) and the **quality processes** (section 5.5 to section 8.5).

Data, Document & Process Management

PANSOPHY

A Process & Data Management Tool

- **Data Management & Storage**
 - subcomponent test data
 - processing & testing procedures
 - Inventory
 - R&D and Production
- **Knowledge Management**
 - to Maximize learning from expensive prototyping and low-volume production
 - **Adopted by other DOE Lab**
 - SNS (Spallation Neutron Source)
 - LCLS-II Cryomodules at JLAB



Data, Document & Process Management

DocuShare Tool

- Web-accessible centralized file storage database (Lab-wide & SRF).
- **Controlled-Sharing** access to site content.
- **Collection-Based** filing structure.
- Files for SRF organizational info, Quality Management System, Project Management, procedures, travelers, etc.
- Plus other account and content features.

The screenshot displays the Xerox DocuShare web interface. At the top, the header includes the Xerox DocuShare logo, user 'jleung', and links for 'Logout' and 'My Tasks'. Below the header, a section titled 'My Background Jobs (24)' features a large image with the text 'Capture, Manage, and Deliver'. The main content area is divided into 'Collections' and 'Other Links'. The 'Collections' section lists various categories with folder icons: '12 GeV Upgrade', 'Facilities', 'Infrastructure', 'Management', 'Outreach', 'Safety and Quality Assurance', 'Science', and 'Security'. The 'Other Links' section includes 'My DocuShare'. A sidebar on the right shows a breadcrumb trail: 'Location: Home » Facilities » SRF Institute Listing'. Below this, a table lists SRF Institute projects, including '01 - SRF Projects', '02 - SRF Technical Facilities', '03 - SRF Organizational Information', '04 - SRF Quality Management System (QMS)', and 'Quick Reference DocuShare Structure'. The bottom of the interface has three tabs: 'Explore', 'Related Links', and 'My Links', each with a list of links.

Pansophy Traveler – An Example

Pansophy
A System of Universal Knowledge

you have been authenticated
who am i click here to logout

MAIN MENU TRAVELERS MENU -> SRF 12 GeV W.F.O. CLOSED PRJ

TRAVELERS

Traveler Area: Edit / View

Search For: C100- (i.e. CAV-INSP)

C100

Select Traveler Page 0 NEXT LAST NEW

SerialNum: 0	Traveler ID: C100-CAV-ASSY2	Rev: R3	Page: 0	Traveler Seq Number: 0
Traveler Title C100 Cavity Assembly, Evacuation, and Leak Test				
Traveler Abstract The following traveler documents the steps for the second of two clean room cavity assemblies for VTA qualification of C100 cavities for the 12GeV project.				
Traveler ID C100-CAV-ASSY2				
Traveler Revision R3				
Traveler Author Steve Castagnola				
Traveler Date 13-May-2011				
NCR Emails castagno,macha				
Approval Names Steve Castagnola Kurt Macha John Hogan				
Approval Signatures				
Approval Date 13-May-2011 13-May-2011 13-May-2011				
Approval Title Author Reviewer Project Manager				
References List and Hyperlink all documents related to this traveler. This includes, but is not limited to: safety (THAs, SOPs, etc), drawings, procedures, and facility related documents.				
RGA Leak Test Procedure C100 cavity evacuation procedure Cavity tooling VTA assembly drawing C100 final cavity assembly procedure for VTA qualification Cavity installation into test stand procedure				
Revision Note				
R1 Initial release of this Traveler.				
R2 Updated C100 Final Cavity Assembly Procedure for VTA Qualification				
R3 Updated C100 Final Cavity Assembly Procedure for VTA Qualification				

Traveler Cover Page:

- Descriptions & approvals.
- **Links to associated procedures.**
- Revision history.

Pansophy
A System of Universal Knowledge

you have been authenticated
who am i click here to logout

MAIN MENU TRAVELERS MENU -> SRF 12 GeV W.F.O. CLOSED PRJ

TRAVELERS

Traveler Area: Edit / View

Search For: C100- (i.e. CAV-INSP)

C100

Select Traveler Page 1 NEXT LAST NEW

Step No.	Instructions	Data Input
1	Record Cavity Serial Number Operators login Record date If for any reason assembly on this cavity is stopped due to a question or problem select the help request toggle. This will trigger a red status on the traveler dashboard showing a work stoppage. When the problem is resolved unselect the toggle for the dashboard status to go back to yellow. Use the D3 button at the top of the page to record a discrepancy or deviation that occurred before, during, or after the assembly.	CAVIN AssemblyTech1 AssemblyTech2 AssemblyTech3 RecordDate (ex format 18-Jun-2005 16:30) HelpRequest Yes No
2	Perform final cavity assembly as per the C100 final cavity assembly procedure for VTA qualification. Use the comment box at the right to record notes, etc. regarding this assembly. Record tophat/input probe test serial number.	VIATHSN FirstAssemblyTech SecondAssemblyTech ThirdAssemblyTech VIATHSN CavityInstallToTestStandComments
4	Evacuate the cavity as per the C100 cavity evacuation procedure. Record date and time of cavity evacuation. Record date and time turbo pump was established to system. Record total system pressure in mbar after turbo pump is operating at full speed. Allow the cavity to pump overnight.	AssemblyTech_1 SlowEvacStart (ex format 18-Jun-2005 16:30) TurboStart (ex format 18-Jun-2005 16:30) TotalPressure1 mbar
5	After cavity has pumped overnight, record total system pressure in mbar. Leak test the cavity as per the C100 leak test procedure. If cavity is leak tight, save and upload the following files: Analog scan with multiplier on (.rga file), leak test summary with graph (.docx file or .jpg), RGA leak test scan (.rga file). If the cavity is not leak tight, initiate a D3 and contact supervisor or lead technician. The leak tested cavity can now be transported to the VTA mezzanine for 120°F bake.	TotalPressure2 mbar FirstAssemblyTech IsCavityLeakTight Yes No Must submit traveler before attaching files. Must submit traveler before attaching files. Must submit traveler before attaching files. LeakTestComment

DATA INPUT –

1. Process instructions & steps to guide work flow.
2. Data Input – **data entry and comments** made by user at prescribed process points.
3. 'Hooks' to inventory system – **automatic serial number push** and **I.D.s** for individual components and assemblies.

Pansophy Traveler – An Example (cont.)

DATA OUTPUT

- **Status Board** - provides snapshot of work-in-process.
- Data Query and Filter Functions for **REPORTs** on selected parameters.
- **Export function** to MS Excel for other data analyses.

The screenshot displays the Pansophy Traveler software interface. The top navigation bar includes 'MAIN MENU', 'QUERIES MENU ->', 'GLOBAL', 'SRF', '12 GeV', and 'W.F.O.'. The 'Status Board' is visible, showing a list of projects and their status. The 'Query Menu' is also shown, with options for 'Variable Grid' and 'User Defined'. The 'Traveler Report' is displayed, showing a detailed table of data for various projects and parameters.

Status Board

TRAVID	trav_seq_num	serial_number	trav_open_who	trav_open_date	trav_close_who	trav_close_date
C100-CAV-INSP	2	C100-RI-002	GEORGED	08/03/10	CARPENTE	10/18/10
C100-CAV-ASSY	2	C100-RI-002	CJOYNER	08/04/10	ABURRILL	12/08/10
C100-CAV-DEGR	4	C100-RI-002	JDAVEN	08/05/10	ABURRILL	12/06/10
C100-CAV-HPR	4	C100-RI-002	STIPTON	08/05/10	ABURRILL	12/06/10
C100-CAV-ASSY2	2	C100-RI-002	DREYFUSS	08/06/10	MACHA	10/25/10
C100-CAV-RFIN	2	C100-RI-002	OVERTONR	09/20/10	MARHAUSE	12/21/10
C100-CAV-DEGR	10	C100-RI-002	JDAVEN	09/21/10	ABURRILL	12/06/10
C100-CAV-DEGR	7	C100-RI-002	JDAVEN	09/21/10	ABURRILL	12/06/10
C100-CAV-HPR	7	C100-RI-002	JDAVEN	09/21/10	ABURRILL	12/06/10
C100-CAV-EPOL	2					
C100-CAV-ASSY	4					
C100-CAV-HPR	8					
C100-CAV-ASSY2	4					
C100-CAV-BAKE	3					
C100-CAV-HEAT	2					
C100-CAV-THKN	2					
C100-CAV-VTRF	4					
C100-CAV-THKN	21					
C100-CAV-TUNE	12					
C100-CAV-INSP2	10					

Traveler Report

Serial	CAVSN	AssemblyTech1	AssemblyTech2	AssemblyTech3	RecordDate	FinalAssyComments	VTATHSN	TotalPressure1	TotalPressure2	IsCavityLeakTight	LeakTestScan	LeakTestComment
1	C100-RI-001	dreyfuss	cjoyner		2010-08-05 07:33:00.0		WG-2	3.3E-008	1.2E-007	Yes		
2	C100-RI-002	dreyfuss	cjoyner		2010-08-06 13:15:00.0		WG-1	6.1E-008	1.4E-007	Yes		
3	C100-RI-001	castagno	cjoyner		2010-09-18 05:48:00.0			0.0002	1.7E-007	Yes		
4	C100-RI-002	castagno	cjoyner		2010-09-23 07:30:00.0		VTA-TH-04	9.2E-005	1.2E-007	Yes		
5	C100-RI-003	castagno	cjoyner		2010-10-04 13:43:00.0			0.00026	1.2E-007	Yes		
6	C100-RI-004	cjoyner		castagno	2010-10-08 09:03:00.0		WG-1		5E-007	Yes		
7	C100-RI-005	cjoyner		macha	2010-10-11 11:38:00.0		VTA-TH-08	1.5E-005	1.9E-008	Yes		
8	C100-RI-006	cjoyner		castagno	2010-10-13 09:24:00.0		VTA-TH-04	1.2E-005	1E-007	Yes		
9	C100-RI-007	cjoyner		castagno	2010-10-18 10:45:00.0		VTA-TH-02	9.3E-005	9.7E-008	Yes		
10	C100-RI-008	cjoyner			2010-10-20 08:59:00.0		VTA-TH-07			No		
11	C100-RI-008	castagno	dia	cjoyner	2010-10-20 09:13:00.0		VTA-TH-07	0.0011	1.2E-006	Yes		
12	C100-RI-006	dreyfuss	cjoyner		2010-11-28 07:16:00.0		WG-1	1	1E-007	Yes		
13	C100-RI-006	dreyfuss	dia		2010-10-31 18:18:00.0		VTA-TH-04	1.2E-005	1E-007	Yes		
14	C100-RI-008	cjoyner	dia		2010-11-17 08:14:00.0		VTA-TH-07	0.00023	1.1E-006	Yes		
15	C100-RI-007	cjoyner	dia		2010-11-22 07:31:00.0		VTA-TH-01	0.00044	3.3E-007	Yes		
16	C100-RI-005	cjoyner	dia		2010-11-23 09:02:00.0		VTA-TH-03	0.00023	2.3E-007	Yes		
17	C100-RI-004	cjoyner	dia		2010-11-24 08:20:00.0		WG-2	1	2.3E-008	Yes		
18	C100-RI-003	cjoyner	dia		2010-12-03 09:31:00.0		WG-3	0.0025	4.4E-007	Yes		
19	C100-RI-004	castagno	dia		2010-12-03 10:07:00.0	Bottom Range was removed from cavity for re-HP.		0.00033	2.3E-007	Yes		
20	C100-RI-010	dreyfuss	dia		2010-12-05 08:02:00.0		WG-1	1	1E-007	Yes		
21	C100-RI-011	dreyfuss	dia		2010-12-05 08:03:00.0		VTA-TH-04	1	2.3E-007	Yes		
22	C100-RI-012	cjoyner	dia		2010-12-07		VTA-TH-08	0.00072	4E-007	Yes		

Query Menu

Variable Grid
User Defined

User Defined Query - (C100-CAV-ASSY2)

Select checkboxes of Variables to be used in Query

Field Name	Query	Field Name	Query
CAVSN	<input checked="" type="checkbox"/>	CavInstallToTestStandComments	<input type="checkbox"/>
AssemblyTech1	<input checked="" type="checkbox"/>	AssemblyTech_1	<input type="checkbox"/>
AssemblyTech2	<input checked="" type="checkbox"/>	SlowEvacStart	<input type="checkbox"/>
AssemblyTech3	<input checked="" type="checkbox"/>	TurboStart	<input type="checkbox"/>
RecordDate	<input checked="" type="checkbox"/>	TotalPressure1	<input checked="" type="checkbox"/>
HelpRequest	<input type="checkbox"/>	TotalPressure2	<input checked="" type="checkbox"/>
Assembly_Tech1	<input type="checkbox"/>	First_AssemblyTech	<input type="checkbox"/>
Assembly_Tech2	<input type="checkbox"/>	IsCavityLeakTight	<input checked="" type="checkbox"/>
Assembly_Tech3	<input type="checkbox"/>	AnalogScan	<input type="checkbox"/>
FinalAssyComments	<input checked="" type="checkbox"/>	SummaryFile	<input type="checkbox"/>
VTATHSN	<input checked="" type="checkbox"/>	LeakTestScan	<input checked="" type="checkbox"/>
FirstAssemblyTech	<input type="checkbox"/>	LeakTestComment	<input checked="" type="checkbox"/>
SecondAssemblyTech	<input type="checkbox"/>	VTATSSN	<input type="checkbox"/>
ThirdAssemblyTech	<input type="checkbox"/>		

Submit

Control of Non-Conforming Product (MAI-P-004)

Non-Conforming Reports (NCRs):

- Formal process for **identification and disposition** of Non-Conforming products.
 - **Process Integration** between quality control, inventory control, and the production Travelers.
 - Tie-ins to Pansophy for **automatic Non-Conforming Reporting**.
-

Detours, Deviations and Discrepancies (D3s):

- A **Supplemental Tool** for capturing “Off-Normal” events that occur before, during or even after the production process.
- Tie-ins to Pansophy for automatic **reports and search query**.

Traveler Reports

Travelers

Travelers (Op/Cl)

[illegible]


Open/Closed status of instantiated travelers

Travelers by Project




Project view of open/closed status of all instantiated travelers

Travelers by Workcenter



Workcenter view op/cl status of instantiated travelers

Travelers Open/Closed by Month



Monthly op/cl status of travelers and accumulate percentage closed

Traveler Weekly Report

[illegible]

Op/cl status for a given week

Traveler Weekly Owners

Select a project

01-17
0.0
0.0

Results: 1000

On an Altair

Refine

Export results to CSV

env name	environment	Host	Project name	Task name	Start date	End date	Env ID	Env ID
LPD-0000	LPD-0000	Host: altair	LPD-0000	LPD-0000	2018-12-12	2018-12-12	0000	000000
LPD-0001	LPD-0001	Host: altair	LPD-0001	LPD-0001	2018-12-12	2018-12-12	0001	000000
LPD-0002	LPD-0002	Host: altair	LPD-0002	LPD-0002	2018-12-12	2018-12-12	0002	000000
LPD-0003	LPD-0003	Host: altair	LPD-0003	LPD-0003	2018-12-12	2018-12-12	0003	000000
LPD-0004	LPD-0004	Host: altair	LPD-0004	LPD-0004	2018-12-12	2018-12-12	0004	000000
LPD-0005	LPD-0005	Host: altair	LPD-0005	LPD-0005	2018-12-12	2018-12-12	0005	000000
LPD-0006	LPD-0006	Host: altair	LPD-0006	LPD-0006	2018-12-12	2018-12-12	0006	000000
LPD-0007	LPD-0007	Host: altair	LPD-0007	LPD-0007	2018-12-12	2018-12-12	0007	000000
LPD-0008	LPD-0008	Host: altair	LPD-0008	LPD-0008	2018-12-12	2018-12-12	0008	000000
LPD-0009	LPD-0009	Host: altair	LPD-0009	LPD-0009	2018-12-12	2018-12-12	0009	000000
LPD-0010	LPD-0010	Host: altair	LPD-0010	LPD-0010	2018-12-12	2018-12-12	0010	000000
LPD-0011	LPD-0011	Host: altair	LPD-0011	LPD-0011	2018-12-12	2018-12-12	0011	000000
LPD-0012	LPD-0012	Host: altair	LPD-0012	LPD-0012	2018-12-12	2018-12-12	0012	000000
LPD-0013	LPD-0013	Host: altair	LPD-0013	LPD-0013	2018-12-12	2018-12-12	0013	000000
LPD-0014	LPD-0014	Host: altair	LPD-0014	LPD-0014	2018-12-12	2018-12-12	0014	000000
LPD-0015	LPD-0015	Host: altair	LPD-0015	LPD-0015	2018-12-12	2018-12-12	0015	000000
LPD-0016	LPD-0016	Host: altair	LPD-0016	LPD-0016	2018-12-12	2018-12-12	0016	000000
LPD-0017	LPD-0017	Host: altair	LPD-0017	LPD-0017	2018-12-12	2018-12-12	0017	000000
LPD-0018	LPD-0018	Host: altair	LPD-0018	LPD-0018	2018-12-12	2018-12-12	0018	000000
LPD-0019	LPD-0019	Host: altair	LPD-0019	LPD-0019	2018-12-12	2018-12-12	0019	000000
LPD-0020	LPD-0020	Host: altair	LPD-0020	LPD-0020	2018-12-12	2018-12-12	0020	000000
LPD-0021	LPD-0021	Host: altair	LPD-0021	LPD-0021	2018-12-12	2018-12-12	0021	000000
LPD-0022	LPD-0022	Host: altair	LPD-0022	LPD-0022	2018-12-12	2018-12-12	0022	000000
LPD-0023	LPD-0023	Host: altair	LPD-0023	LPD-0023	2018-12-12	2018-12-12	0023	000000
LPD-0024	LPD-0024	Host: altair	LPD-0024	LPD-0024	2018-12-12	2018-12-12	0024	000000
LPD-0025	LPD-0025	Host: altair	LPD-0025	LPD-0025	2018-12-12	2018-12-12	0025	000000
LPD-0026	LPD-0026	Host: altair	LPD-0026	LPD-0026	2018-12-12	2018-12-12	0026	000000
LPD-0027	LPD-0027	Host: altair	LPD-0027	LPD-0027	2018-12-12	2018-12-12	0027	000000
LPD-0028	LPD-0028	Host: altair	LPD-0028	LPD-0028	2018-12-12	2018-12-12	0028	000000
LPD-0029	LPD-0029	Host: altair	LPD-0029	LPD-0029	2018-12-12	2018-12-12	0029	000000
LPD-0030	LPD-0030	Host: altair	LPD-0030	LPD-0030	2018-12-12	2018-12-12	0030	000000
LPD-0031	LPD-0031	Host: altair	LPD-0031	LPD-0031	2018-12-12	2018-12-12	0031	000000

Currently open travelers listed by authors

NCR Reports


NCRs

NCRs (Op/Cl)

Table with columns: Project, System, Work Center/Activity, Status, Date. The table lists various NCRs and their current status (Open, Closed, etc.).


Open/Closed status of instantiated NCRs

NCRs by Project




Project view of open/closed status of all instantiated NCRs

NCRs by Workcenters




Workcenter view op/cl status of instantiated NCRs

NCR Classification (Traveler)




NCR classifications listed by traveler with filters on system and op/cl status

NCR Classification (Project)




Pareto chart of NCR classifications

NCR Closure Periods & Age



NCR time elapsed from instantiation to closure

NCR time elapsed from instantiation to present time



Status Boards and Drilldowns

Status Boards

The figure displays three status boards. The first board, titled 'Status of cavities from RI', shows a grid of cavity status for various cryomodules (C1 to C10) and cavities (C1 to C10). The second board, titled 'Status of cavities from EZ', shows a similar grid for cavities from EZ. The third board, titled 'Status of cryomodule completion', shows a grid of completion status for various cryomodules (C1 to C10) and cavities (C1 to C10).

Monthly Statement

Drilldowns

Cavity level components and key parameters.

Diagram of a cavity string level component showing various parts: Flange Long, HMT, HMTB, HMTA, valve, AF15, and CAV.

Part	Serial	Part	Serial	Part	Serial
FLANGE LONG	1000000000	HMT	1000000000	HMTA	1000000000
HMT	1000000000	HMTB	1000000000	valve	1000000000
HMTB	1000000000	HMTA	1000000000	AF15	1000000000
CAV	1000000000				

Cavity String level components and key parameters.

Diagram of a cavity string level component showing various parts: Flange Long, HMT, HMTB, HMTA, valve, AF15, and CAV.

Part	Serial	Part	Serial	Part	Serial
FLANGE LONG	1000000000	HMT	1000000000	HMTA	1000000000
HMT	1000000000	HMTB	1000000000	valve	1000000000
HMTB	1000000000	HMTA	1000000000	AF15	1000000000
CAV	1000000000				

Diagram of a cryomodule level component showing various parts: Flange Long, HMT, HMTB, HMTA, valve, AF15, and CAV.

Part	Serial	Part	Serial	Part	Serial
FLANGE LONG	1000000000	HMT	1000000000	HMTA	1000000000
HMT	1000000000	HMTB	1000000000	valve	1000000000
HMTB	1000000000	HMTA	1000000000	AF15	1000000000
CAV	1000000000				

Cryomodule level of key parameters and serial numbers, allowing a user to drilldown to subcomponents.

Summary

- Resources for C75 cryomodules are well understood
 - Based off of C50 refurbishment program – 13 CM completed
 - C75 introduces new cavity shape, modifications to tuner ends and supports for HOM elbows
- LCLS II will bring challenges to C75-01 (and possibly C75-02)
 - C50-13 was completed on schedule in the midst of LCLS II
 - CPP is top priority for the Lab, LCLS II is also a high priority
 - Stretching out C75-01 helps manage resource loading
 - May need to add resources depending on LCLS II future work
 - If LCLS II is extended, HE is added
- A plan has been made to meet the CPP for FY18 and beyond
 - Strategically start cryomodules ahead of FY installation dates
- The SRF organization and means for completing cryomodule assembly projects is well established and experienced
 - Completed about 60 cryomodules
 - Currently working on C75-01 (currently in the books as C50-13)
- SRF quality systems are established, C75 specific in progress

Backup

Back Up - C50/C75/C100

From Accelerator "STAY Treat" July 2015) - see Slide 6

	# Cav	cells /cav	cav length m	Active Length m	fill factor %	MV	volts /cav (MV)	gradient (MV/m)	klystron power	unit cost (FY16 M\$ Direct)	RF Cost	Total Cost FY16 Direct	MV (gain)	V(gain) /\$
C50	8	5	0.5	4	48.1	50	6.25	12.5	6	1.51			20	13.3
C75 [†]	8	5	0.5	4	48.1	75	9.4	18.8 [‡]	8	1.91			45	23.6
C100 [‡]	8	7	0.7	5.6	64.4	100	12.5	17.9 [‡]	13	4.77			70	14.7

Update - January 2016

	# Cav	cells /cav	cav length m	Active Length m	fill factor %	MV	volts /cav (MV)	gradient (MV/m)	klystron power	unit cost (FY16 M\$ Direct)	*RF Cost	Total Cost FY16 Direct	MV (gain)	V(gain) /\$
C50	8	5	0.5	4	48.1	50	6.25	12.5	6	1.23		1.23	20	16.3
C75 [†]	8	5	0.5	4	48.1	75	9.4	18.8 [‡]	8	1.73	0.77	2.50	45	18.0
C100 [‡]	8	7	0.7	5.6	64.4	100	12.5	17.9 [‡]	13	4.30	1.56	5.85	70	12.0

Update - February 2018, with new vendor quotes for C75 & C100

	# Cav	cells /cav	cav length m	Active Length m	fill factor %	MV	volts /cav (MV)	gradient (MV/m)	klystron power	unit cost (FY18 M\$ Direct)	*RF Cost	Total Cost FY18 Direct	MV (gain)	V(gain) /\$
C50	8	5	0.5	4	48.1	50	6.25	12.5	6	1.42		1.42	20	14.1
C75 [†]	8	5	0.5	4	48.1	75	9.4	18.8 [‡]	8	1.76	0.84	2.60	45	17.3
C100 [‡]	8	7	0.7	5.6	64.4	100	12.5	17.9 [‡]	13	4.57	1.81	6.38	70	11.0

What changed from August 2015 to January 2016 ?

- C75 & C100 - Addition of RF (assumes C50 still usable)
- C75 - Improved estimate for in House Fabrication and other costs

*New cells or new processing required to achieve higher Q's and gradients

*Engineering required at additional cost (not included)

‡Digital LLRF required

Ref. DRAFT C50 vs C75 vs C100 Rev 49- 13Feb2017

What changed from January 2016 to February 2018 ?


- C50 & C75 - Mag shielding & NEG Pumps added
- C75 - Actual Vendor Quotes for Cavity Fab, Ingot & Ingot Slicing (reusing end groups)
- C75 & C100 - LL RF based on cost estimate from C. Hovator (June 2017)
- C100 New Vendor (1-CM) quotes (Aug 2017) for Nb & Cavities, He Vessel, Tuners, Thermal Shield, Magnetic Shield, Vac Vessels

What is not included ?

- One time R&D costs for Cavity Development (already done)
- One time cost for LL RF Engineering & Development to address obsolesce (same design for C50, C75 and/or C100 zones)
- Wave Guide Vendor Development + 8 Wave Guides



Approx. Labor for CM Projects



Projected C75 Labor by Resource Type

	C75-01 FTE												
	Jun '18	Jul '18	Aug '18	Sep '18	Oct '18	Nov '18	Dec '18	Jan '19	Feb '19	Mar '19	Apr '19	May '19	Jun '19
Scientist	0.00	0.00	0.01	0.01	0.01	0.01	0.02	0.02	0.02	0.01	0.01	0.01	0.01
ComSci	0.00	0.00	0.01	0.01	0.01	0.01	0.02	0.02	0.02	0.01	0.01	0.01	0.01
ElcEng+EACII	0.00	0.00	0.01	0.01	0.01	0.01	0.02	0.02	0.02	0.01	0.01	0.01	0.01
ElcTec	0.01	0.03	0.06	0.06	0.10	0.10	0.17	0.15	0.15	0.10	0.10	0.07	0.06
MecEng+MACII	0.02	0.04	0.07	0.07	0.12	0.12	0.20	0.17	0.17	0.11	0.11	0.09	0.07
MecTec	0.07	0.15	0.31	0.31	0.52	0.52	0.86	0.73	0.73	0.49	0.49	0.37	0.31
Sr Staff	0.01	0.01	0.03	0.03	0.05	0.05	0.08	0.06	0.06	0.04	0.04	0.03	0.03
Misc	0.00	0.01	0.01	0.01	0.02	0.02	0.04	0.03	0.03	0.02	0.02	0.02	0.01
	0.12	0.25	0.50	0.50	0.85	0.85	1.40	1.20	1.20	0.80	0.80	0.60	0.50

Derived from C50-11 actuals

Cost and FTE for C50-11, 12 and 13

								Direct \$	
1.04.09.002	C50-11		FY13	FY14	FY15	FY16	FY17	Total Cost	
		Labor	\$ 762.250	\$ 74.155	\$ 13.023	\$ -	\$ -	\$ 849.428	
		Non-Labor	\$ 263.372	\$ 4.788	\$ -	\$ -	\$ -	\$ 268.160	
		Total	\$ 1,025.622	\$ 78.943	\$ 13.023	\$ -	\$ -	\$ 1,117.588	
		FTEs	8.59	0.57	0.09	-	-	9.25	
1.04.09.004	C50-12		FY13	FY14	FY15	FY16	FY17	Total Cost	
		Labor	\$ -	\$ 153.683	\$ 153.070	\$ 519.033	\$ 36.468	\$ 862.254	
		Non-Labor	\$ -	\$ 62.269	\$ 105.208	\$ 161.721	\$ 0.907	\$ 330.105	
		Total	\$ -	\$ 215.952	\$ 258.278	\$ 680.754	\$ 37.375	\$ 1,192.359	
		FTEs	-	1.39	1.38	5.87	0.38	9.02	
1.04.09.010	C50-13		FY13	FY14	FY15	FY16	FY17	FY18	Total Cost
		Labor	\$ -	\$ -	\$ -	\$ -	\$ 363.508	\$ 18.504	\$ 382.012
		Non-Labor	\$ -	\$ -	\$ -	\$ -	\$ 211.607	\$ -	\$ 211.607
		Total	\$ -	\$ -	\$ -	\$ -	\$ 575.115	\$ 18.504	\$ 594
		FTEs	-	-	-	-	4.07	0.16	4.23

C50-13 NP Actuals (\$575k direct)

C50-11 and C50-12 actuals were each ~ \$1,150k direct


Differences with C50-13 explains cost

- Started out as a C50 cryomodule (C50-7), not a C20
 - Minimal cavity processing was required to regain the gradient
 - Lower cost to recover the cavities (\$108k for C50-13 vs. \$370k for C50-12)
- AIPNCP was created and used to cover the cost of the “C75” cryounit
 - Cost for roughly one-fourth of the module refurbishment was shifted to AIP(\$324k direct in FY17)
- Acceptance testing was not preformed in the CMTF (~ \$47k direct)
- Commissioning will be done in FY18 (~ \$34k)


FY18 Plan for CM Refurbishment

- Cost for C50-11 and C50-12 was about \$1150k, each
- Use AIP funds to purchase and qualify (8) upgraded cavities
 - Industry provides fabricated cavities
 - Process and test in house
- Use NP funds to refurbish the C20 cryomodule
 - Same as C50-12 for example minus cavity processing and testing
- Amount needed from NP is $\$1185\text{k} - \$350\text{k} = \$835\text{k}$
- Amount needed from AIP is $\$250\text{ (buy)} + \$370\text{k} = \$620\text{k}$


CM Prep-Test FTEs by AWP Skill per Pay Period (WBS 1.4.6.8)




CM Cav String Assembly FTEs by AWP Skill per Pay Period (WBS 1.4.6.9)



CM Assembly FTEs by AWP Skill per Pay Period (WBS 1.4.6.10)



CM Test FTEs by AWP Skill per Pay Period (WBS 1.4.6.11)



M:\LCLS-II\PMO\Manpower\PMO Working Files\LCLS-II Semi-Monthly FTEs Skill Mix Chart_FY18-Master_Extended.xlsx

1/24/2018