

# $^3\text{He}$ target tests

Kai Jin

University of Virginia

June 15, 2018

# Status

- ▶ Oven Installation
- ▶ change of EPR
- ▶ Water NMR
- ▶ Beam compensation

## Installation of oven

- ▶ The new oven is installed in target lab in EEL building(the size is bigger than old one.)




Figure 1 : oven

## change of EPR system

- ▶ EPR RF coil move from inside oven to outside oven: longer distance between RF coil and pumping chamber;
- ▶ Use lens to focus D<sub>2</sub> signal to fibers, then use thick fiber transport to photodiode: need to improve light collection efficiency to ensure signal-to-noise ratio.





Figure 2 : EPR system

# EPR coil optimization

By change turns of EPR coil, can optimize coil impedance, and reach maximum RF signal at pumping chamber.



test condition: wire gauge 24 awg. RF generator give -4 dBm RF signal, Lockin sensitivity 1mV.



coil turns (N)	R( $\Omega$ )	L( $\mu$ H)	signal Vpp ( $\mu$ V) at a RF gain			
			20% RF gain	40% RF gain	60% RF gain	80% RF gain
1	0.10	0.3	14	43	90	160
3	0.20	3.1	17	49	101	180
4	0.23	5.4	150	450	830	1650
5?	0.26	8.1	130	380	770	1250
6	0.30	11.0	110	320	625	1000


# EPR light collection

Combine simulation with tests, find the configuration: Len1: focal length=150 mm, Len2: focal length=30 mm can optimize the light collection efficiency. Still need to test with fiber-bundle in the new oven setup.



## water NMR

- ▶ To calibrate  $^3\text{He}$  NMR, need to measure thermal polarization of proton in deionized water,  $P_{thermal} = \tanh(\frac{\mu_p B}{k_B T})$ . For a holding field  $B = 18$  Gauss,  $T = 395$  K,  
 $P_{thermal} = 6.23 \times 10^{-9}$ .
- ▶ resonance field for RF frequency 91 kHz is 21.27 G;
- ▶ RF generator: 500 mV (rms), 90.7 kHz;
- ▶ RF amplifier: 10% of max gain;
- ▶ Preamplifier: 10k-100k bandpass filter, x100 amplification;



# Spin up and spin down sweep

Still need to reduce noise to finish the water calibration.




Figure 5 : Sweep up fit




Figure 6 : Sweep down fit



# Beam compensation

- ▶ Unpolarized laser gets polarized after optics first;
- ▶ Finally send laser to pumping chamber by mirrors;
- ▶ Dielectric mirrors conserve power but not phase;
- ▶ Different phase shift for S and P waves;
- ▶ Circular  $\rightarrow$  elliptical polarization;
- ▶ By add an another  $1/4$  wave plate into setup: have an extra degree of freedom.

