



BAND: Installation and Readout

Florian Hauenstein, ODU

Efrain Segarra, Jackson Pybus, MIT

CLAS Meeting 11/15/18

BAND in Hall Context




BAND Layout

Plastic scintillator detector

- Covers 160 to 170°
- 40% neutron efficiency
- 116 7.2 x 7.2 cm² bars
 - two 2" PMTs per bar
 - 3 scintillator lengths (51, 164 and 202 cm)
 - BC-408 Scintillant
- Hole for beam line


Veto layer

- 2 cm x 7.2 cm
- one 2" PMT per bar
- 24 PMTs



BAND Construction

- July:
 - Glue PMTs to bars
 - Test bars and fix light leaks
 - Assemble all bars and some Veto bars into frame
- August:
 - Transport to the hall
 - Install cables and electronics
- First data taking with cosmics
- Still need (in January)
 - Optical fibers for laser calibration system
 - More mu-metal shields
 - More readout channels






BAND is finished

BAND in the Hall



Transport to
the hall






DAQ Full Setup



Left side PMTs (116 chan.)
+ 12 Veto Layer channels

Right side PMTs (116 chan.)
+ 12 Veto layer channels




- 1 VXs crate for FADCs
- 1 VME crate for TDC and discriminators
- Splitters between crates
- Groups of 16 channels from nearby PMTs (besides Vetos)
- Detailed mapping files available for each signal

VME crate with FADCs (7), Disc (8) and TDC
(Trigger board not in the picture)



DAQ Fall Setup

- 40% instrumented
- Trigger:
 - stand-alone readout or
 - combined with CLAS
- Extra Trigger board for Fall-2 setup




Electronics and Cables




Item	Count	Progress
Signal long cables	256	100%
Signal patch panel connectors	256	100%
Splitters	256	100% available (50% installed)
Discriminators	16	8 installed in fall (rest available)
TDC	2	1 installed in fall (rest available)
FADC	16	7 installed in fall, waiting for repairs of rest
Cable splitter to FADC	256	50% done, rest in production
Cable splitter to Disc	256	50% done, connectors for rest ordered
SHV crate and modules	2 + 11	2 + 9 installed (1 in repair + 1 ordered)
SHV long cables	256	100%
SHV patch panel connectors	256	100%
VXS crate and CPU	2	CPU delivered, VXS should arrive next week



Patch Panel



- 2 long and 2 short panels
- 2 Fiber patch panels
- Panels and frames finished
- Installation in January





Setup 1 - Fall 18

- Startup with only 65 PMTs equipped with available mu-metals, mainly inner PMTs of short bars
- Simple trigger (any PMT fires)
- Stand-alone readout

Correlated neutrons with PCAL during beam setup



Beam to BSY dump



Setup 2 – Fall 18


- Mu-metal shields on PMTs Row 10 and below
- Readout both sides
 - short bars in row 11 to 15
 - long bars 410 and 510
 - 4 short bars in row 16
- Cosmics trigger with at least 3 coincidence bars per column

ADC spectrum with cosmics




Rates with beam at 45nA


Setup 2 – Fall 18 (PMTs with shields)




Setup 2 – Fall 18 (readout PMTs)



BAND HV GUI





Left and Right side of each column + Veto



Detailed GUI to control each channel

BAND Scaler GUIs




Summary

- Total of 116 scintillator bars (+ 24 vetos in BAND)
 - 58 long ones (2m and 1.6 m) + 12 Veto
 - 58 short ones (0.5 m) + 12 Veto
- BAND installed in the hall (without all Veto bars)
- ~40% cabled up for fall for background studies and commissioning
- Mapping files available for next year as well as fall
- Data available with standalone triggering on cosmics
- Readout of BAND with CLAS is available, tests in the next days




VETO LAYER




MAIN DETECTOR
(TOW DIFFERENT TYPES
OF PMTs)

- R_{in} fully used and Part of other short and long bars
- 7 FADCs total
- L4-7 means splitter not fully cable strang
- Need mu-metal installed

- L4: $(1-5)10_L + (1-5)(11-12)A_L + \text{free}$
- L5: $(1-5)(13-15)A_L + 416A_L$
- L6: $(1-5)(11-13)A_R + 316A_L$
- L7: $(1-5)(14-15)A_R + (1-4)16A_R + (1-2)16A_L$




Fall 18 Signal channels
(group of 16)






VETO LAYER




MAIN DETECTOR
(TOW DIFFERENT TYPES
OF PMTs)


- L_{in} and part of R_{out} used (maybe Layer 1 instead of 5)
- R5-7 means splitter not fully cable strang itself
- R4 only TDC and trigger




- R4: (1-4)(10-12B)_R (only TDC)
- R5: (1-5)(13-15)B_R + 116B_R
- R6: (1-5)(11-13)B_L + 510_R
- R7: (1-5)(14-15)B_L + (1-4)16B_L + 5(11-12)B_R



Fall 18: Signal channels (group of 16)



Row labeling for each column (5th column without row 15-18)



Veto Row labeling

