


BONUS 12
**(BARELY OFF-SHELL NUCLEON
STRUCTURE @ 12 GEV)**
PROCEDURES AND STATUS

Ibrahim H. Albayrak

Hampton University



PHYSICS REVIEW

- Proton structure have been studied in great detail.
- Much less is know about neutron structure due to lack of free neutron target
- Neutron structure can be studied using DIS on deuteron target by tagging the recoiled proton using RTPC.
- The momentum of spectator proton is used to interpret initial momentum of the neutron which is weakly bound to the deuterium target
- Selecting backward, low momentum spectator protons minimizes:
 - -Off shell effects
 - -Final state interactions




PHYSICS REVIEW

- BONuS12 expected results



PHYSICS REVIEW


- **BONuS12 extends BONuS6:**
 - Improved momentum resolution with Increased drift region from 3 cm to 4 cm
 - Improved **W** resolution with better momentum reconstruction
 - Increased gain
 - Reduce material and better reconstruction algorithm allowing lower threshold momentum of proton.
 - Better track sampling
 - Better acceptance in phi
 - Higher rates, higher statistics with increased detector length, increase luminosity to $2 \times 10^{34} \text{cm}^{-2} \text{s}^{-1}$




BONUS12 EXPERIMENTAL SETUP



BONuS12 in CLAS12

- Moller electrons bottled up by Solenoid field around target
- Solenoid field allows momentum determination







BONUS12 RTPC



BONUS12 RTPC





GAS CIRCULATION



BONUS12 RTPC CONSTRUCTION

RTPC CONSTRUCTION

- Detector design is complete




BONUS 12 ASSEMBLY TOWER

Detector assembly station

Actuator assembly for vertical GEM foil removal and placement

GEM foil HV test station

Wrapping and gluing station for GEM foils, pad board and cathode



RTPC CONSTRUCTION


- Ready to go:
 - Clean room environment
 - Automated wrapping/gluing station
 - Puller assembly
 - HV testing station
 - RTPC assembly station
 - Pad board surface uniformity scanner
 - Tested construction procedure

**Puller
assembly**

**HV test
station**

**Detector
assembly
station**

**Wrapping/gluing
station**



**Detector construction stations
at Hampton University**



RTPC CONSTRUCTION

- **Tooling and procedures for wrapping cylinders well tested**
- **We completed a mechanical assembly test of a 3 layer GEM assembly, including connection to the HV board**
- **HV connection procedure, assembly of chamfer, US field cage, HV board, US plate mounting hardware complete**
- **Currently forming GEM cylinder layers and mounting on chamfer assembly**
- **First assembly including mounting of US endplate done by end of June in advance of padboard delivery.**


RTPC CONSTRUCTION

- Cathode Assembly
 - Construction procedure tested
 - Assembly station is constructed
 - Complete construction by mid July

Cathode foil field cage electrical connectivity test





Cathode and ground foil assembly




Cathode foil wrapping station

RTPC CONSTRUCTION

- GEM foils, read out board, cathode assembly, Wrapping/gluing





Automated Epoxy applicator

Gluing arm stepper motor


Mandrel rotation stepper motor

RTPC CONSTRUCTION

Automated epoxy application




GEM foil wrapping and gluing




RTPC CONSTRUCTION

GEM foils held by the puller assembly



HV test box

• **HV Testing**



**Detector base
(Chamfer +
Field cage +
HV bord)**

• **Installing
GEM cylinder**

RTPC CONSTRUCTION

Self aligning puller assembly




Removal of glued capton cylinder using puller mechanism






RTPC CONSTRUCTION




Assembly Station with storage box




Can rotate around two axes and moves in one dimension




RTPC CONSTRUCTION

- **Readout 'padboard'**
 - Fabricated, delivered, tested for continuity and shorts. We have electrical connectivity after wrapping for better than $>99.5\%$ of the pads all the way to the end of the adapter boards
 - Successfully tested wrapping into cylindrical geometry (next slide).
 - Currently having surface connectors mounted
 - Expect complete board beginning of July
 - Wrap first detector board and mount installation ring in early July
- **Current limiting adapter boards**
 - Design completed.
 - Prototype of short board received and tested for continuity and shorts
 - Checked that board inserts easily into padboard without distorting shape and remains firmly connected.




**Readout adapter board
with current limiting circuitry**





- **Prototype read out board on surface uniformity scanner and control software**
- **Meet the required geometric uniformity (a few hundred microns variation)**

RTPC TEST SETUP IN EEL



DAQ AND RECONSTRUCTION SOFTWARE



- **We are working with Saclay (Irakli Mandjavidze) on completing the update on FEU and BEU firmware to accommodate simultaneous readout of the RTPC and the FMT.**
- **We will be doing extensive tests of the whole DAQ chain in the EEL, initially with the EG6 prototype and starting in mid-July with the “real” RTPC. We will use both cosmic rays and sources, and look for reconstructed tracks.**
- **The data analysis software is close to complete - pattern recognition and helix fitter work and are fast enough for our expected data set. We are ironing out some small remaining compatibility issues and expect to integrate the software into the official CLAS12 coatjava release later this summer.**
- **First round of simulations is done; will repeat with higher statistics and more realistic detector soon.**

SUMMARY


- **Real BONuSI2 RTPC construction has started:**
 - **Construction of the Inner core of the detector (GEMs+Chamfer+HV assembly) has started and will be ready by the end of the month**
 - **Final Padboard + Readout adapter boards will be ready by the end of the month**
 - **Cathode assembly will be ready early next month**
 - **Gas panel, slow controls, HV and DAQ in the EEL are being tested with the EG6 prototype**
 - **The BONuSI2 RTPC is expected to be ready to be tested in mid July**

BACK UP SLIDES

UP STREAM FIELD CAGE



DOWN STREAM FIELD CAGE



PHYSICS REVIEW

- BONuS6 measured neutron SFs ratio: F_2^N/F_2^P





Figure: N.Baillie et al., PRL 108(2012)199902


PHYSICS REVIEW

- Direct measurement of neutron would lead to a better understanding of:
 - Neutron SFs
 - Test the predictions for d/u when $x \rightarrow 1$
 - SU(6), spin flavor symmetry $1/2$
 - Hard gluon exchange, helicity conservation $1/5$
 - Scalar diquark dominance 0


Figure: The figure of projected 12 GeV u/d ratio extractions comparison by Dr.A.Accardi




DOWN STREAM END EXPLODED



DOWN STREAM END






UP STREAM END EXPLODED




Gas Electron Multipliers (GEMs)

F. Sauli et al., NIMA 386 (1997) 531



- Holes chemically etched in kapton layered front and back with copper.
- Gas amplification due to large local field in holes.
- More amplification from more GEM layers.
- Can operate at very high rates.
- Can conform to curved geometries
- Configurable charge collection (strips vs pads)




UP STREAM END



DOWN STREAM END



PADBOARD SURFACE UNIFORMITY TESTS



Control software

Actuator assembly

Probe

Stepper motor

Rotary table