

# Update on Polarized $^3\text{He}$ Target

Jian-ping Chen, Jefferson Lab

A1n/d2n Collaboration Meeting, July 24, 2019

- Target for A1n/d2n
- Current status
  - Engineering/mechanical
  - Target system
  - Polarimetry and Tests
- Plan

# Polarized He3 Target for A1n/d2n

## Hall C A1n/d2n goals:

- 30 uA on 40 cm , ~10 atm,  $L \sim 2.2 \times 10^{36} \text{ cm}^{-2} \text{ s}^{-1}$
- In-beam polarization ~ 55 %,
- Polarization measurement precision ~ 3%
- Except each cell last for about one month beam needs ~ 6 cells for both A1n/d2n + spares

# Update on target status

## Status on target system, polarimetry, controls:

- Target system fully functional
- Tests, calibrations and studies on going at JLab target lab:  
Cell testing/optimization (**Mingyu Chen** and **Junhao Chen**)  
test on Savior completed, water calibration next  
will continue test on Fulla (once it arrives from UVa)
- Pulse NMR (**Mingyu**), Lock-in/DAQ system working now
- EPR (**Melanie Rehfuss**), new fiber connection for EPR light detection working now. EPR calibration on Savior with various conditions complete
- Control/EPICS (**Junhao, Arun Tadepalli, Brad, ...**)
- Instrumentation location, layout, cabling (**Junhao**)
- Safety/trainings

# Update on components

## Status on laser, fibers, optics:

- **9 Lasers/long fibers/in hand. Will order more laser as spares.**
- **4-1 combiners tested. Works well with slight temperature increase. Connection with long fibers, slight mis-match in size. Vendor agreed to replace with same size as long fibers option/backup plan: long fibers fuse to 4-to-1 combiner.**
- **Some short fibers coating slowly deteriorating**
- **Compensating optics for transverse pumping**

# Cells, Mechanical Parts, Installation, Documents

## Current Status on cell production, mechanical, ...

- Target cells (Gordon Cates talk)
  - W&M group joined production Jan/Feb
  - Speed up the pace for cell production, ~ 1 cell every 2 weeks
  - 4 usable cells (~ 40-50 %) as of 2 weeks ago
- Updated design and installation design all complete
  - Mechanical parts ordered/arrived for installation
  - Parts in storage available and checked
- Installation plan and preparation (**Walter's talk**)
- Documents: target OSP and LSOP approved (needs update)

# On Site People Power and User Activities

**At JLab: students + engineer/designer + JP + ...**

- **Three graduate students + 1**

**Junhao Chen (W&M, Todd's group)**

**Mingyu Chen (Uva, Xiaochao's group)**

**Melanie Rehfuss (Temple, Zein-Eddine's group)**

**Roy Murchhana (Kentucky, Wolfgang's group) (end of August?)**

**Arun Tadepalli (JLab postdoc), Brad Sawatzky (controls)**

**At user target labs :**

- **Uva (Gordon Cates):**  
**cell fabrication (Gordon's talk)**
- **W&M (Todd Averett)**  
**Reference cell system/cooling jets testing (Todd's talk)**  
**cell fabrication**
- **Kentucky (Wolfgang Korsch)**  
**field direction measurement (Roy Murchhana's talk)**

# Plan

- **Complete testing:**
  - **Complete full testing of Savior (1<sup>st</sup> cell)**
  - **Water calibration in target lab cross calibration with EPR**
  - **Test Fulla (another reasonable cell)**
  
- **Installation, control system, cell production and field mapping:**
  - **Move out target lab once hall is open (August 5<sup>th</sup>?)**
  - **Assistant with installation**
  - **Control system /EPICS**
  - **Cell production continue at UVa/W&M with an accelerated pace of 1 cell every 1-2 weeks**
  - **Prepare for target field mapping with compensation coils/Bender magnet**
  - **Make system ready for field direction measurement**