




Beamline performance

Rafayel Paremuzyan

HPS collaboration meeting Nov 15-18, 2021


Beamline Engineering drawings






Before sending the beam to the FCup the beam first sent to the tagger dump:


- To make sure halo counts are not too high
- Beam positions on harps are where they are supposed to be
- The position on the tagger viewer is correct
 - There was an instance when 2 A difference in the tagger magnet current made the significant vertical beam spot shift on the tagger viewer






Beam Tuning: Beam to Faraday Cup

First week was not easy. There were significant tails at 2H02. This was fixed on Sep. 9. The throught the whole run we didn't have any significant issues on the beam profile on the HPS side.






Beam width at 2H02 and at the target






Up until Sept 23 we were positioning the beam on SVT at X=0 \pm 200 μ m Y=0 \pm 50 μ m

On Sep 23 Tim and Cameron proposed to move the beam up by 119 μ m in order to have an equal acceptance for tracks in the bottom and top halves of SVT





The beam blocker attenuation



3.7 GeV at 120 nA requires the beam blocker

Before starting production runs, we calculated the beam blocker attenuation for each target.


Significant dependence on the target thickness. Thicker target scatters more and in addition the magnetic field spreads them more and by pass the beam blocker.






Beam position stability

We have about 50% better beam stability at 2H02 compared to the 2016 run.





After long downtimes, most of the time we just did one harp and SVT wire scans just to confirm beam position, we almost didn't lose time tuning the beam




One pass beam


Oct-18 to Oct 25 We run one pass beam: 1922 MeV


• We were able to get the beam back to FCup only couple of days after, but it was related to various accelerator issues: LCW leak etc...

Beam quality wise: There was no any issue with the pass1 beam





- Similar beam stability
- We run 70 nA
- We did not use FCup







Beam time structure













- Chicane improperly rumped up
- BPM freeze out
- Vacuum



Chicane







Only Frascati field is affected.

Note: those runs are still valid runs, but might need special MC, and perhaps different cuts for Beam Spot Constrain candidates.

On Sep. 21, Before Chicane mis-setting



On Sep. 22, after mis-powering the chicane



16 prod. runs affected, and highlighted in the run spreadsheet.



Beam position freezout






This issue occurred during previous runs as well.

MCC folks with Calvin installed poly blocks in front of BPM receivers, thinking this might be a radiation issue, though it didn't actually help.



Vacuum issues




2H00 pump failed on Nov.4. Within a week we got a good vacuum again.



Summary

- Very good beam profile throughout the entire run
 - $\circ \sigma_{\gamma} < 50 \,\mu m$
 - Beam stability < 10 μ m



- Most of the time we just did single harp and SVT wire scans just to confirm beam profile
- No significant downtime because of the beamline

