

# A New System for MgB<sub>2</sub> Coating R&D at LANL


Tsuyoshi Tajima, Leonardo Civale, Torben Grumstrup, Dan Kelly, Maxim Mealy,  
Paolo Pizzol\*, Anju Poudel, Harry Salazar, Roland Schulze (LANL, \*now at SNS)  
Hiroshi Sakai, Hayato Ito, Eiji Kako, Takafumi Okada, Kensei Umemori (KEK)

TFSRF 2022 Workshop, 19-23 September 2022

LA-UR-22-29668

# Background

- $\text{MgB}_2$  could be useful if we can run the cavity at  $\sim 20$  K with cryocoolers




[T. Tajima, Teikon Kogaku 57 (2022) 23, DOI: 10.2221/jcsj.57.23]

## Background (Cont.)


- After evaluating  $\text{MgB}_2$  film samples prepared with different techniques since ~2005, we concluded that it is worth trying to coat a full-size cavity.
- Although we think HPCVD and Reactive Co-evaporation are the best techniques, we decided to start with a 2-step technique due to its simplicity.
- The 2-step technique consists of coating B layer on the cavity inner surfaces in the first step, then react it with Mg vapor in the second step. See the next slide.
- We started with the second step first using B films we obtained in the previous project that ended in 2015.
- Since we lost a large furnace in 2015, we used a small tube heater and tested the reaction of B with Mg vapor starting in 2015 with promising results [Tajima et al. SRF2015 p. 700]
- The  $\text{MgB}_2$  project funding at LANL ended in 2015, but we got a new funding from DOE through the US-Japan Cooperation Project. (H. Sakai is Japan PI) from 2018.
- We continued the B-Mg reaction tests with good results of  $T_c$  up to ~38 K [Pizzol et al. SRF2021]
- DOE funding was not large enough to build a new system, but the good results led to a larger LANL internal funding to be able to build a new system that will be shown in this workshop with the first B-Mg reaction test conducted recently.

# Concept of our 2-step coating process


[2]



B-Mg reaction test set up with a small tube heater [Tajima et al., SRF2015, p. 700]



6mm x 6 mm samples



**B-Mg reaction tests using the small tube furnace since November 2019. The B films we have been using are those taken from the 1.3-GHz cavity used during the previous project that ended in 2015.**

Sample ID	Run# (date)	Reaction temperature (°C)	T <sub>c</sub> (K)	Notes
3-A3	16 (27NOV2019)	750	33.3	
3-A4	16 (27NOV2019)	750	36.8	
1-E3	17 (20JAN2020)	700	35.3	
1-E5	17 (20JAN2020)	700	38.0	
1-E7	18 (15-16MAR2020)	650	35.5	Held for ~21 h
1-E8	18 (15-16MAR2020)	650	37.0	Held for ~21 h
1-F1	19 (23OCT2020)	700	37.9	Slow cooling
1-F3	19 (23OCT2020)	700	35.6	Slow cooling

**Due to COVID-19, no tests were performed between March and September 2020.**

The nominal holding time is 1.5 h.

All but run #19 were fast cooling, i.e., <20 min to <40 °C.


So far, 700 °C coating seems to be the best.

The difference in T<sub>c</sub> in the same test seems to be due to the difference in the substrate.

# The new system

- The design was performed with US-Japan Cooperation Project, but there was no funding to build it.
- We got an internal funding in FY21 and started purchasing components.
- The major component was a large main furnace, and it was ordered to a U.K. company through a U.S. company.

# A 3D model of the new $\text{MgB}_2$ coating system at LANL. A ventilation system to handle toxic $\text{B}_2\text{H}_6$ gas has been installed.





# The main furnace was delivered in September 2021 but found damaged in transit.



The initial scheduled delivery date was June 2021, but it was delayed due to COVID-19.

This furnace was returned to the company in U.K. and repaired and returned to LANL in late January 2022.

**Some photos of the new ventilation piping. The new ventilation system cleared intentionally created smoke inside the booth in 3 min.**

**A panoramic view of the PVC piping**



**outside**




**Scrubber**



## Some recent photos



Dr. Sakai measuring some dimensions




The plumbing for B coating has not been done yet.

## We started testing the main furnace in July 2022

- Raised the furnace temperature up to 800 C and found that the Viton o-ring at the end flanges got damaged due to too high temperature, probably much higher than its limit of ~205 C.
- Added 3/8" OD copper cooling pipes around the beam pipes outside the furnace.
- We tested up to 700 C with the flange cooling and the Viton o-ring was not damaged.




Damaged Viton o-ring




Cooling pipe added



**We performed our first B-Mg reaction test on 28 July 2022.  
Three B coated Nb samples were attached at 3 locations on a  
1.3-GHz 1-cell Nb cavity.**



**Four new Mg pellets were placed on a Nb tray on a Mo boat in a section next to the cavity**



Mo boat

Nb tray



These cutouts are to pump down the cavity



# This time, the sample coupons were Nb coated with B.

A sample looking from outside.



Sample holder parts

Inconel 718 (spring material that works up to 1200 F)

316 SST

Substrates were ~2 mm thick Nb this time

6 mm x 6 mm c-plane sapphire substrate

2-M3 threaded holes


Part 1

Part 2

Part 3

Cavity surface hole

(this hole is an inch size hole for the Nb cavity)





# Furnace temperature trend during the first B-Mg reaction test


The furnace was turned on with 150 C setting at 06:53:55 at 27 C on 28JUL2022.

It reached ~150 C at 06:59:00, i.e., it took 5 m 5 s. It overshoot to 160 C.


The set temperature was raised to 700 C at 09:19:50, i.e., it was kept at 150 C for 2 h 20 m 50 s.

It reached 700 C at 11:18:50, i.e., it took 1 h 59 m 00 s.

The furnace was turned off at 14:20:13, i.e., it was kept at 700 C for 3 h 1 m 23 s.



The degassing at 150 C was probably not long enough.  
We should have waited until the pressure goes down.



# Magnetometer measurements on the 3 samples were performed on 12-13SEP2022 with no superconductivity detected.

- One thing we noticed was that the cavity outer surface color changed after this reaction, then after heating under vacuum.



After B-Mg reaction in Ar at 700 C (furnace)




After heating at 700 C under vacuum



**We did not analyze the surface material after the B-Mg reaction test but did analyze the surface after heating the cavity under vacuum.**

XPS analysis at LANL



The surface material is Nb oxide ( $\text{NbO}_2$  and  $\text{Nb}_2\text{O}_5$ ).

Indium is seen since the sample was placed into indium foil.


**We also measured temperatures at various points in the Inconel pipe when the furnace temperature went up to 700 C**



A K-type thermocouple is being attached at the cell equator




**Photos of the samples after the B-Mg reaction test. No pics were taken before. XPS surface analysis will be done soon.**




**It was found that the Mg section, cell and beam pipe temperatures are considerably lower than the furnace temperature (<532 C vs. 700 C)**

With 1 atm  
Ar inside



**The oxidation may have been due to the air trapped at the port for introducing Ar gas.**






## Conclusion and near-term next steps

- We were able to build a new system for the full-size 1.3-GHz cavity coating R&D in the SRF lab at LANL and started B-Mg reaction tests.
- The first B-Mg test was unsuccessful with no superconductivity detected on all the 3 samples.
- We measured the temperatures on the cavity, Mg section, etc. and found that the temperatures were  $<532$  C when the furnace temperature was 700 C, which is likely to be the cause of failed test.
- Next steps
  - Add RGA sensor at the pump port (ongoing)
  - Analyze the surfaces of recent samples (XPS analysis ongoing)
  - Raise the temperature of the Mg section and cavity to  $\sim 700$  C. We need to improve the cooling of flanges so the flange temperature will not exceed  $\sim 200$  C (Viton limit).
  - Add a pumping at the port for introducing Ar gas
  - Continue preparing for the B layer coating. Since diborane ( $B_2H_6$ ) gas is toxic, we will need to be very careful to ensure safety.

# US-Japan Cooperation Project Schedule (in the official proposal). Mg-B reaction tests continue first.

This will be delayed



# Acknowledgments

- We would like to thank Stephen Milton, the previous division leader at the Accelerator Operations and Technologies Division at LANL, for his enthusiastic support that led to the LANL internal funding.
- This R&D have been supported by the US-Japan Science and Technology Cooperation Program in High Energy Physics and LANL LDRD project 20210720ER.

# Backup slides

# Temperatures of cavity, Mg section, etc. when the furnace temperature went up to 700 C. Comparison between vacuum and 1 atm Ar inside.

- The Mg section temperature (Ch1, orange) got lower with 1 atm Ar from 531 C to 503 C
- The Inlet BP Top temperature (Ch2, gray) got lower with 1 atm Ar from 516 C to 485 C.
- The flange temperature (Ch6, dark blue) did not change much.
- Ch4 is probably not showing correct temperature.

Ch1 (Orange) : Inside Mg section

Ch2 (Gray): Inlet BP Top


Ch3 (Yellow): Cell Top

Ch4 (Light blue): Outlet BP top

Ch5 (Green): Inconel pipe inner surface

Ch6 (Dark blue): South flange

vacuum



With 1 atm Ar inside

