


# MOLLER Status Report


Hall A Collaboration Meeting

June 2022

MOLLER – a precision measurement of  $A_{PV}$  in  $e^-e^-$  scattering




Fixed Target Polarized  
Electron-Electron Scattering



$$A_{PV} = \frac{\sigma_R - \sigma_L}{\sigma_R + \sigma_L} = -mE \frac{G_F}{\sqrt{2}\pi\alpha} \frac{16 \sin^2 \Theta}{(3 + \cos^2 \Theta)^2} Q_W^e$$

$$Q_W^e = 1 - 4 \sin^2 \theta_W \sim 0.075$$

Jim Fast – MOLLER Project Manager



# MOLLER – World leading measurement of $A_{PV}$


- MOLLER aims to measure the parity violation asymmetry in  $\vec{e}-e$  or Møller scattering at 11 GeV

$$A_{PV} = \frac{\sigma_+ - \sigma_-}{\sigma_+ + \sigma_-} \rightarrow A_{exp} = \frac{Y_+ - Y_-}{Y_+ + Y_-}$$

- $A_{PV} = A_{exp} \sim 32 \text{ ppb}$ ,  $\Delta A_{exp} \sim 0.8 \text{ ppb}$
- $A_{exp}(Qweak) \sim 226 \text{ ppb}$ ,  $\Delta A_{exp} \sim 9.3 \text{ ppb}$
- The MOLLER experiment aims to achieve an order of magnitude better absolute precision than the Qweak completed measurement

11 GeV, 65  $\mu\text{A}$  90% beam polarization  
 $A_{PV} \sim 32 \text{ ppb}$        $\delta(A_{PV}) \sim 0.8 \text{ ppb}$   
 $\delta(Q^e_W) = \pm 2.1 \% \text{ (stat.)} \pm 1.1 \% \text{ (syst.)}$





See presentation “MOLLER Physics” by Zuhal Demiroglu tomorrow at 15:30





# Target system schematic






- Integrated piping schematic
  - Vacuum system (warm)
  - H2 piping (warm)
  - He Piping (cryo)
  - Target loop (cryo)
- DA = D. Meekins
- Design pressures
  - H2 piping 150 psi
  - He piping 300 psi
  - Vacuum -15 psi
  - Target loop 100 psi
- Vacuum is insulation for Loop and He piping.
- All pumps, reliefs, blowdowns are vented to atm
- Exhaust piping is purged with inert gas to stack.
- Stack has 1.5 psi EOLR







# Target system elements

- Heat exchanger (5 kW cooling power, assessed with CFD)
  - ASME stamped vessel
- LH2 Pump (25 liters/s@4psid)
  - Case, impeller, shaft and motor
  - Very similar to Qweak pump with room temperature motor, not cold
- High power heater (4 kW, assessed with CFD)
- Solid targets (as requested by Collaboration, will be assessed with CFD)
- Piping: connecting loop components
- Cylindrical target Cell: 125 cm long, 7.6 cm  $\varnothing$ 
  - Extensive CFD to model the cell fluid space



# Target cell CFD calculations support design goals


## MOLLER Cell Model 21 Flow Space



LH2 flow profile in horizontal cross-section, zooming in at cell windows

LH2 flow profile in vertical cross-section, zooming in at cell windows


Temperature profile snapshot in beam-in nipple




$$\Delta T_{max} \sim T_{wall} - T_{sat}$$

- For beam-in window  $\Delta T_{max} \sim 9 K$

Temperature profile snapshot in beam-out nipple




- 4x4 mm<sup>2</sup> raster area
- For beam-out window  $\Delta T_{max} \sim 22 K$
- The conditions for reaching CHF for LH2 are not met





# Spectrometer separates signal from background with ~100% acceptance



Acceptance defining collimator


## Other parts of the experiment

- Integrating detectors
- Tracking detectors
- Beam monitors
- Shielding
- Target


## Spectrometer Elements

- Set of resistive toroidal magnets (US and DS)
- 2 collimators to define the acceptances
- Beam pipe and enclosures
- collimators to control backgrounds
- Blockers to study backgrounds
- Lintels and "collars" to shield coils and detectors

Full azimuthal acceptance  
for mollers from  
 $6 < \theta_{lab} < 20$  mrad




particle envelopes  
along beamline



Coils in one septant

# Upstream toroid and collimator region

The purpose of the collimators is to absorb scattered electrons and gamma radiation, combined with the bending of the spectrometer fields, to selectively exclude unwanted signals from the detectors




**Sieve Collimator**  
Array of high-aspect ratio holes  
1mm-10mm

**Collimator 1-2**  
Complex 4-piece brazement with internal cooling passages



**2-Bounce Shield**  
Long, self-supporting / structural piece

**Collimator 4**  
500mm diameter, 500 kg



**Blocker Collimator**  
Cooled during operation






In this analysis, the coolant channel is kept at a constant 30 °C. This is reasonable since at the expected 4 GPM flow rate, the delta T across the blocker is only 0.95 °C, and the Reynold's number is very high indicating a high convective coefficient, thus, temperature gradients in the fluid and cooling channel can be neglected. The results of the FEA show very low temperature rise in the collimator, about 14.3 °C.








# Primary collimator design and engineering

- Primary tungsten and copper collimator receives ~5 kW of deposited power
  - ~4 kW on long central tungsten tube, ~1 kW on acceptance defining section (W+Cu)




- Disc: 300mm dia x 150mm thick
- Core: 59mm dia x 575 mm long
- 90W 10Cu
- Min Density 17 g/cc
- Absorbs 4500 W in core, 900 W in disc
- +/- 100 um on petal surfaces
- +/-50 um on core inner profile, which has several different tapers along length
- Copper cooling fittings brazed to drilled holes
- Multiple water-vacuum braze interfaces
- Leakage between inlet and outlet channels is permissible, but ideally avoided where possible
- Temperature during operation: 30 - 150 C
- Radiation dose 6.6e11 Rads






Maximum Tungsten Temperature	147 C
Maximum Water Temperature (20 C inlet)	53.2 C
Pressure drop	170 kPa (24.6 psi)
Water Temperature Rise	4.6 C

# Upstream toroid design is underway, but behind other designs in maturity









# Downstream toroid design is maturing well



B: contact conductivity = 1 W + mid frame cooling  
 Temperature  
 Type: Temperature  
 Unit: °C  
 Time: 1 s  
 Custom  
 Max: 54  
 Min: 27  
 5/9/2022 5:17 PM





# Downstream torus coil prototyping is nearing completion


Conductors




Coil winding mandrels



Brazing Qualification Parts



Conductor Insulation Wrapping



Sub-coil 1, 2 and 3 after winding



# Potting compound irradiation tests

- Coils are potted with CTD-403 cyanate ester resin
  - Selected for extreme tolerance to radiation – developed for ITER
  - Prior post-irradiation strength tests all done in LN (77K)
  - Atmosphere during irradiations not well documented
    - Found a publication suggesting less damage during irradiation under vacuum vs inert gas or air
- MOLLER conducted set of tests closer to our conditions
  - Samples under vacuum (MOLLER condition) and inert gas (likely prior test conditions)
  - Wanted to tie to existing data at ~50 MGy and fill in data gap between 50 and 240 MGy
  - Testing done at slightly elevated temperature expected in MOLLER operations (~38 C)
- Multi-institution effort
  - Sample fabrication and testing done by the resin manufacturer (Composites Technology)
  - Encapsulation in quartz ampoules (vacuum and N<sub>2</sub> gas) by Twinleaf (glass blower)
  - Irradiations done at UC Davis Triga reactor (can hold 3 sets of samples in core)
  - (5) sets of samples irradiated
    - Air and vacuum to ~50 MGy (actual 41 MGy) and 100 MGy (actual 84 MGy)
    - Vacuum to 124 MGy (left in reactor for both irradiations in center location with highest flux)










# Test results better than anticipated

## Confirmed publication hypothesizing less degradation for irradiations in vacuum

- Solid red curve is ITER data measured at 77 K
- Red dashed curve is the ITER data scaled for temperature dependence to 38 K using historical measurements of unirradiated samples - *what we were expecting going in to tests*
- Red dotted line uses our unirradiated strength value to scale the ITER low dose values
- Blue is our measurements of samples irradiated under vacuum
- Orange is our measurements of samples irradiated in N<sub>2</sub>
- Critical data for design of coil shielding





# Beampipe, bellows and pion donut support are all coming together well






# Drift pipe exit window - will be building a scaled test article




Rolled & Welded Pre-prototype Thin Window





Detector window

Prototype window





D: 44 psi  
 Maximum Principal Stress  
 Type: Maximum Principal Stress  
 Unit: MPa  
 Time: 1  
 Max: 186.73  
 Min: -24.729



# Tracking (GEM) detector design

- GEM trackers will be used to image scattered electrons during low current calibration runs
- Trackers are retractable during normal high current running
- Trackers sit on rotating wheel support system so all azimuths can be covered
- Design of both linear (radial) motion system and support of sectors (two BGEMs plus a trigger scintillator) have matured significantly since the preliminary design review
- GEM prototyping will be underway shortly at both UVA and Stonybrook
  - NSF is funding UVA (4 sectors)
  - DOE is funding SBU (3 sectors)





# Detector region has evolved considerably


- Main detectors and Shower-Max integrated on “rotator” so all modules can be installed from above rather than needing complex materials handling to insert, e.g. from underneath the structure
- Requires robust, simple cable disconnects
  - Each 1/28<sup>th</sup> module has 8 detectors
  - One connector can provide all HV, one for LV, and one each for the two signal paths

## Quadrax/Twinax Connector Series





MIL-DTL-38999 Style Connectors



## MHC Contacts




# Latest beam test at Mainz – MOLLER ring 5 and 6 modules





# Hall A Moller beamline – target moved 4.5 m upstream from pivot



Final Moller Beamline Design  
(Prelim ACC-000-2845-0036)

- Majority of New Design Scope is located in Regions 1 and 3
  - Existing Hall A Moller polarimeter Quads, Dipole and Detector box are unaffected and will remain in place
  - New Unser box (Unser-BCM-BCM) will use commercial “Unser”; has ½ the current noise of the Hall A unit
- Region 1 section being assembled and installed ahead of main MOLLER down as “prototype”
  - Improves beamline performance for SBS-era experiments
  - Gain operational experience with new beamline and instrumentation prior to MOLLER engineering run
  - Reduces work coordination issues in Hall A during the MOLLER installation down (i.e. shortens long down period)

# Hall A entrance beamline for MOLLER – prototype procurement progress



Pedestal, Stand Platform and Braces Stored in Test Lab High Bay




Girder/Vacuum Hardware

MCG Coils Currently being Fabricated at Technicoil, along with QR Coils to replace Spare QR that will be used for Moller Beamline.



MCG Magnet Steel Components



Girder Base Plates



# MOLLER – a DOE Major Item of Equipment (MIE)

- Falls under DOE-O-413.3B Change 5





Figure 2. Typical DOE Acquisition Management System for Other Capital Asset Projects (i.e., Major Items of Equipment and Operating Expense Projects)


# Funding outlook

- FY20 funding was \$2M (TEC)
  - All carried over to FY21 – awaiting CD-1 approval for spending this flavor of funding
- FY21 funding was \$5M
  - \$3.2M carried over to FY22
- FY22 funding President's Budget Request was \$7M
  - **Actual appropriation was only \$5M**
  - **Still ample to get the project through CD-2/3**
- Challenge is going to be FY23 where we requested ~\$14M
  - We need ~\$8M to stay on schedule
    - Any less and we will have to slip the schedule one year
  - **President's Budget Request supports only \$4M** [worst case scenario]
    - Estimate is that we will have >\$2.5M in carryover to help us through FY23
    - We can maintain the team and get through this lean year, but funding will be very tight
  - Congressional marks are not available yet
    - **Congress funds science very well**
    - We are awaiting news on House and Senate marks (typically come out during the summer)



# Summary

- We have been making steady progress since CD-1; continue to be on track towards CD-2/3 Spring 2023
- We had a very successful set of Preliminary Design Reviews over the past several months
- FY22 allocated funding is sufficient for us remain on course to CD-2/3 with minimal impact on CD-4, but current President's Budget Request for FY23 would result in a 1 year delay
- The tight integration we have of the scientists and engineers on MOLLER is essential
  - Reviewers, DOE and NSF have all commented favorably about this!
- But much work remains to be done to complete final designs and navigate DOE reviews...



See presentation “MOLLER Physics”  
by Zuhail Demiroglu tomorrow at 15:30