
## **CEBAF Accelerator Status, June 2024**

Presented by Michael Tiefenback

Most materials gathered by Eduard Pozdeyev, plus material from other "involved parties"

CLAS Collaboration, June 25, 2024









## **Presentation Content**

- Obligatory accelerator site schematic
- Mission; long-term plans and projects
  - Positrons mentioned, leading into e- energy straggler/degrader
- Accelerator Performance to date
- Upgrades energy reach, 200 keV injector, target irradiation, etc.
- Limitations and outlook
- Miscellaneous other upgrades and developments








## **CEBAF Accelerator**

- SRF, recirculating, 5.5 pass, 12 GeV Linac
- Beam power up to 900 kW
- Total recirculated beam current in each linac up to 450 uA
- CEBAF can provide beam up to 4 Halls simultaneously
- Beam can be extracted to a specific Hall at any selected pass
  - e.g., Hall A can operate at pass 4,
    Hall B can operate at pass 5, and
    Hall C can operate at pass 3



# COMPETENCY PLAN

Develop Pause and Restart Plan

Feedback/
Notable Event
Investigation of
LOTO Observations

Update LOTO and pre-job brief Policy

Develop priority list of projects to determine order of competency evaluations

> Develop Competency Evaluation Plan

Baseline current active locks and correct any deficiencies

**Assess Current PPE** 

Record a "Day in the life" demonstration for simple/complex LOTO Execute competency evaluation process based on activity priorities

**GOAL: WEEK** 

OF 6/10


Individuals can begin executing HEC LOTO

We would welcome the help, so please reach out to your DSO!



## Alignment with Lab's Mission and Long-Range Plan (LRP)

 LRP Recommendation 1: Capitalize on the extraordinary opportunities for scientific discovery made possible by the substantial and sustained investments. Continue effective operation of national user facilities, including CEBAF at TJNAF



From S. Henderson's all-hands presentation 07/2023

- Operate CEBAF for Nuclear Physics for >30 week/yr. for >1800 users
- Support 12 GeV experimental program (MOLLER, SoLID, K-Long) [and eventually e+]

Computational Nuclear Physics

Theory and computation supporting

NP goals


## **CEBAF Performance Plan (CPP)**

- Established in 2017 with goal of achieving 12 GeV in 5.5 passes with good reliability.
- Reliability Project, manager: Randy Michaud
  - Critical Spares
  - Klystrons
  - Obsolescence
  - Optimal Weeks Hardware
- Energy Reach Project, manager: Tony Reilly
  - C75 program


C100 refurbishment program

CPP funding vs FY. The total is \$60.1M.

- Plasma processing



## **CPP Energy Reach Project Is Critical For Success**




- 1. C75-03, C75-04, C100R + 44 MeV Plasma Processing
- 2. C75-05, C75-06, C100R + 15 MeV PP SL
- 3. C75-07, C100R + 15 MeV PP NL
- 4. C75-08, C100R + 15 MeV PP SL
- 5. C75-09 (+ Booster)
- 6. Steady State: C100R + 15 MeV PP Each linac alternating years

Required CEBAF Energy Reach with margin can be nearly achieved in FY 26 and exceeded in FY27 with the proposed profile.



## FY 2023 SAD Cryo-module Dance (past tense)



Note: Cryomodule MeV recorded from 1/23/23 data

# FY 2024 SAD Cryo Module Dance (happening)

1L09

C50@ 0 MeV

#### **Overall for NL**

- Install C100-08R into 1L22: +23 MeV
- Install C75-03 into 1L09: +70 MeV
- Results in a potential gain of ~ 93 MeV

**Out for Rebuild** 

1L05

C75@ 60 MeV

# 70 MeV C100-08R C75-03 Out for Rebuild 1L10 1L22 C75@ 57 MeV C100@ 75 MeV


Process 1L05 and 1L10 (C75s) in the NL

**Plasma Processing Plans** 

Process (TBD) C100s in NL

## **Overall for SL**

- Install C75-04 into 2L05: +50 MeV
- Results in a potential gain of ~ 50 MeV




Note: Cryomodule MeV recorded from 12/18/23 data



# **CEBAF Energy Reach Evolution and Next Year Projection**

CPP stopped and turned around energy degradation and reliability decrease




Jefferson Lab

Energy reach corresponds to 10 RF trips/h for zero beam current.

Maximum beam energy Is lower for a high beam current because of insufficient RF power.

# CEBAF Performance Last Run, thru May 2024

- Energy per linac: 1047 MeV
- Hall A
  - 10 45 uA, pass: 2-4
- Hall B
  - -50 200 nA, pass: 3-5
- Hall C
  - 5 80 uA, pass: 3-5
- Hall D, successful short test run
  - Added to the schedule
  - 4 days, 200 nA, pass 5.5



# High Power Beam Test, 5/20/2024

- 85 uA beam current to Hall C @ 5 pass => 900 kW
- 860 kW for 2 min (1L22 RF trip), 800 kW for 3 min (1L23 RF trip)
- Maximum beam power was limited by available RF power
- We need a few days of sustained effort to push power beyond this level after SAD



## Reliability Comparison FY24 to FY23

- Significant improvement in RF, Beam Transport, and Magnet reliability
  - Improvement due to focus on maintenance, beam tuning, and their optimization
  - Added accelerator gradient to CEBAF during last SAD
  - Lower beam intensity this run
- Apart from (far out of the ordinary) gun problems, reliability would be at 83.5% in FY24


Category	FY23 Downtime, h (/%)	FY24 Downtime (h/%)	Progress (in relative terms)
RF	300 (7%)	222 (4%)	-37% ↓
Beam Transport	244 (6%)	156 (3%)	-45% ↓
Magnets/DC	229 (5%)	72 (1%)	-73% ↓
Gun	2 (0%)	353 (7%)	+16717% ↑
Scheduled hours	4307	5027	

<--non-recurrent



# Weekly CEBAF Reliability Last Run (08/26/2023 – 05/20/2024)

- Two significant downtime events that impacted reliability
  - Gun field emission, Nov/Dec 2023, and
  - Gun laser shutter failure, Mar/Apr 2024



Gun field emission required reducing gun HV and injector energy.

#### Root cause:

Design and test processes for the new gun did not follow best engineering practices.

Gun laser shutter was not in the right position after maintenance and failed to stop the laser beam, causing beam strike event.

#### **Root causes:**

- 1) Inadequate configuration control
- 2) Gun laser system can fail and send full beam for tens of milliseconds without ability to stop it.



## **Accelerator Performance Limitations**

#### SRF

- C100 cavity gradient degradation due to field emission and linac contamination
- Loss of cryomodules and cavities to vacuum leaks and other events
- Cavity faults caused by microphonics and other effects.

#### • RF

- Performance of C100 RF stations lags relatively to the requirement
- Loss of RF stations during run
- C20, C50, C75 Klystron degradation needs attention
- Outdated and inadequate accelerator systems, limit understanding of the machine, postmortem capabilities, and application of advanced techniques such as AI/ML
  - LLRF, earlier, analog versions are still prevalent at CEBAF
  - BPMs, slow DAQ (most), no buffering for postmortem processing
  - BLMs, slow DAQ
  - (No) Global timing system to synchronize CEBAF systems





## **Challenges And Risks**


- Impact of delayed and reduced budget in FY24
  - Unable to procure and install all-metal gate valves this SAD due to late arrival of funding and procurement freeze. This delays effort to mitigate gradient degradation in CEBAF by a year.
  - Delay in refurbishment of klystrons (CPP). Risk of losing potential vendor for klystron refurbishment.
  - 50% reduction in funding of the CPP Obsolescence program. Risk of catastrophic failures increases.
- Safety issues have negative impact on operations
  - Take focus and effort away from operations and reliability
  - Make SAD and maintenance work planning and execution difficult
- Risk: insufficient CPP funding
  - Insufficient funds for CPP can further affect our ability to address energy reach and reliability gaps
- Risk: Insufficient funding of AIPs, favorable Scenario 2 does not materialize
  - Upgrade of LLRF, BPM, BLM, Timing System can be significantly delayed limiting our ability to improve CEBAF performance



## About every 5 years we have a major polarized source advancement
















C. Hernandez-Garcia, "Polarized Sources R&D Overview" HEP visit January 31, 2024 17/29

Jefferson Lab

## We are preparing to install a new, larger photogun for operation to 200 kV








Present CEBAF 130 kV photogun

New CEBAF 200 kV photogun




## The CEBAF design allows for a photocathode preparation chamber behind the gun


#### New photogun electrostatic fields at 200 kV MV/m 10 --12.1 ---18.2 --9 — -24.2 --30.3 --36.4 --42.4 --48.5 --54.5 --60.6 --66.7 --72.7 --78.8 --84.8 --90.9 --103 --109 <del>---</del> -115 --121 --127 --133 --139 --145 --152 --158 ---164 --170 --176 <del>---</del> -182 ---188 ----194 <del>---</del> -200 —







# **Upgraded Injector Solenoids – as-built error corrected**






# Injector Solenoids – improper winding cut-out filled in






# Injector Polarized Solid Target irradiation station installation



# Injector Polarized Solid Target irradiation station installation




## LDRD: Degraded electron beam transport in CEBAF

- Positron source at CEBAF will have higher emittance
- "Degrader" to increase emittance of CEBAF electron beam to match positron beam
  - carbon target, 2 apertures
- Installed between injector booster and first cryomodule
- Tune mode beam to 123MeV dump, NL during beam studies

#### Status: June 21, 2024

- Apertures fabrication and alignment nearly finished
- All other systems ready for installation
- Vacuum work planned following gun work





# Vacuum Events in March

- Shortly after the end of the short run there was a beam strike event on Saturday March 16 at the entrance to the BSY, causing a small loss of vacuum
  - This was due to tune beam being left on an already weakened pipe longer than it should have
  - Fixed using a sealant, physics resumed by Monday
- On March 21 there was a different vacuum event in the northeast spreader
  - Sealant did not work, the chamber was replaced with a spare necessitating a short SAD
  - During this mini-SAD the machine was mostly down, we did not staff 24/7 for several days, and we ran a lot of beam studies that didn't require beam

# Vacuum Event in March







## Benefits Of Advancing LLRF, BPM, BLM, and Timing System


- LLRF Upgrade
  - Provides advanced functionality for field control and diagnostics capabilities.
  - Upgrade in progress. Installation to proceed until 2027.
- Next Generation BPMs
  - Addresses obsolescence. Provides new functionality: high bandwidth DAQ, buffering, interface to global timing system, suitable for capturing fast transients.
  - Porotype construction in progress. Plan to install by 2028.
- BLM System Upgrade
  - Provides new functionality (faster DAQ, buffering, interface to timing system). Total loss monitors can extend area coverage.
- Global Timing System
  - Synchronizes instrumentation and allows correlating their response to beam events
- These systems will benefit CEBAF the most if they are treated as parts of an integrated system, complementing each other.
- Advanced functionality and global timing will provide insight into machine behavior and allow us to use modern tools such as ML/AI.

N. Rider




LLRF v3

New gen. BPM prototype



Global timing system concept





## Helium Vapor Return mass flowmeter installation




- Hot-wire anemometer (Superconducting probe loop, Hyperboloid LLC)
- Competes 3K vapor refrigeration against supplemental heater
  - Static conduction/natural convection/forced convection
- Track and measure heat to maintain partially normal-conducting probe
- Includes a diode thermometer to measure vapor temperature
- Fast (time scale of minutes) measurement of RF cavity dissipation (Q<sub>0</sub>)

# Helium Vapor Return flowmeter, LCLS module May 15, 2024

Various horizontal lines In the legend are labeled as 20/30/40/45/50 Watts of resistor heat. These levels provide an intercalibration between the module resistors and the flowmeter chassis.

When the cryo-system is steady-state, as for these data, one can compare RF-induced flow quite closely to Ohmically induced reference values.



Sample Count (10 Hz data rate)

## **Path Forward**

- Continue critical CPP effort to close energy and reliability performance gaps
- Reestablish CEBAF SRF cleanness effort, implement it as part of CPP, and include plasma processing into operations
- Review and improve CEBAF RF performance
- Improve beam transport and tuning procedures and ensure continuity of experience with machine tuning within AD
- Focus on improving reliability, restore reliability team, and continue effort to turn maintenance from reactive to proactive
- Upgrade CEBAF accelerator system through AIPs and expedite upgrades if possible
- Develop Accelerator Management Plan that will summarize CEBAF path forward for next five years (by end of CY24)