Coordinate Detector Update

Peter Monaghan

Ralph Marinaro, Jacob Bird, May Degilio, Gabriel Womelsdorf

Christopher Newport University

SBS Collaboration Meeting, 12th September 2024



Coordinate Detector Status Update

 Scintillator detector with wavelength shifting fibers used as lightguides

Left/Right split by mirror


Paddles have angular spread ±17°

• Detector over 3 m tall; active 104 \times 294 cm^2

6 modules; 14 maPMTs per half module


2352 channels in total







Detector Configuration




Moving Out of Test Lab to Hall A





Workspace in Hall A






• Finishing light-tightness, magnetic shield and cable installation in the hall.




CDet Installation



- CDet will be attached to Ecal
- Preferred arrangement for ease of moving during kinematic changes
- Required a rethink of cable installation
 - Twice as many cables required now!
- Install patch panels on four racks
- Located to account for interference at pivot.
- Three modules will be installed on an engineered assembly as single plane.
- Assembly will be installed on the full detector frame (which is attached to ECal).


CDet Cable Layout



- **BLUE**: SHV
- around and under pivot, up to LHRS.
- **GREEN** : Signal
- run to lower platform
- RED : Low Voltage
- NINO power supplies in small bunker.
- External SHV and signal cables prepared.




Equipment Layout in the Hall





Modular Low Voltage Power Supply





Internal Cables Complete

SHV for PMTs

Signal from NINO card NINO power for half module Individual NINO power









Software Development

- Working on update of CDet in G4SBS
- Evolution of standalone CDet G4 code developed by Ed Brash
- Use simulation to generate pseudo-data to test the analysis software
- Develop calibration code
- Timing calibration; HV adjustment; gain matching and efficiency;
- Determination of reaction plane angle (with ECal)
- Code for analysis of detector performance
- Online replay plots for shift workers



Status Summary

- Ralph Marinaro (CNU Postdoc) leading day-to-day project management at JLab
- Students have been very busy making LOTS of cables
- Internal cables patch panel to module/PMT/NINO complete
- External cables mostly complete
- 84 Robinson-Nugent splice ribbon cables (VETROC connection UConn supplied connectors) under construction
- Detector modules now in hall \rightarrow light-tightness, magnetic shield and cabling.
- Engineers have design for assembly frame, absorber and attachment to ECal.
- Software development ramping up.
- Thank you to Lawrence, Zak and the rest of Hall A Tech Staff!

