


A detailed 3D CAD model of the PRad-II Gas Target assembly. The model shows a complex arrangement of cylindrical components, flanges, and a central blue and cyan assembly. The background is a light blue gradient.


PRad-II Gas Target Status

Xiangdong Wei
Jefferson Lab

PRad-II/X-17 collaboration Meeting
03/03/2025



Target Designs



Upstream Pump
1450 l/s


Beam-Left Pump
2700 l/s for H₂

Beam-Right Pump
2700 l/s for H₂

Downstream Pump
1450 l/s


5 Turbo pumps around the target:


Both 2700 l/s turbo pumps are backed by a 1900l/s turbo pump and then fed into a multi-stage roots pump.




Target Parameters

- **Target cell:** 75 mm x 75 mm x 40 mm,
- **Thin end walls:** 63mm dia. by 7.5µm thick polyimide foils,
- **"Windowless"** ---Beam enter and exits via 2 mm holes on the center of Kapton foils,
- **Target Material:** High-purity hydrogen gas (>99.99%),
- **Target Length:** 40 mm,
- **Target Pressure:** 0.63 mBar,
- **Target Temperature:** Regulated at 20K,
- **Vacuum Vessel Pressure:** 6.8×10^{-4} mBar.






Brief Target History



- Used for PRad experiment in 2016,
- Major components were kept in a storage place with for future use,
- Some components were repurposed,
- The components were moved the ESB,
- The target were reconnected for testing.





Short Term Plan (11/11/2024)

- Powering up all components,
- Testing each pump separately (to avoid rushing for long lead time repair works),
- Running all pumps and leak check the target setup,
- Establishing remote control for the hall operation (needs help),
- Testing target performance with ^4He (use 2 x flow to compensate low H_2 pumping rate),
- Adding Scintillators and testing vacuum performance (under Youri's guidance and help),
- Ready for ERR in Q2 FY2025,



Status Today—completed task

- **All components were connected and powered, except a few gauges (April arrival),**
- **Water chillers have been operational and provide adequate flows for the pumps,**
- **Original power distributor is in use while Big Bertha is modified for covering all pumps,**
- **All pumps were tested (with interlock bypassed) for <1 hour,**
- **All components can now be controlled by the PC (thanks to DSG),**
- **DSG is now working with Chris Carlin on the Labview control program,**
- **Motors for the target position controllers.**



Status Today—ongoing and later tasks

- **Waiting for arrival of long lead components (middle April delivery),**
- **Working on the Labview control program (DSG, target group),**
- **Working on interlock system,**
- **Run the entire target system with local PC, and later remote PC,**
- **Sending target operation parameters to EPIC system,**
- **Testing target system with veto counter assembly,**
- **Preparing for Hall-B installation.**




Status Today—Target Team

- **MSU:** Bhesha Devkota,
- **JLAB:** Phillip Dobrenz,
Tsuneo Kageya,
Pablo Rojas,
Anil Panta,
Donald Williams,
Xiangdong Wei,
- **UMass:** Andrew Schick.

Team members work on the target system at 5% ~ 50%.




Target Schedule without Veto Counter





Target Schedule with Veto counter






Things might affect the schedule

- **Building Irradiation Cryostat and prepare additional vent line at CEBAF Injector for preparing polarized LiD target for PAC approved experiment, and for DOE funded Polarized Fusion Project.**
- **Veto counter delivery time will drive the final test schedule, which may impact the Hall-B installation schedule.**



Forward Thinking

- The target performance is relied on the 2 existing Pfeiffer HiPace 3400 turbo pumps (no long available on the market). A spare turbo pump is purchased by Duke University.
- The 1900 l/s turbo pump and the multi-stage roots pump (Pfeiffer A 803H) can be replaced by a larger multi-stage roots pump with 2 X pumping speed (Pfeiffer A 1804H). Discussions with the vendor for detailed clarification and quoting are ongoing.
- All turbo pumps and the cold head compressor need chilled water to run, therefore a spare chiller might be a reasonable thing to have. It can also be used for backing up the HyCal chiller.



Summary

- **The target is set up in the ESB for recommissioning,**
- **The performance test without Veto counter package is scheduled to finish in May, before ERR (05/09/2025),**
- **The hall installation will start at the beginning of the next SAM.**
- **Spare equipment has been purchased or being discussed.**