

Upgrade of BEPC-II LLRF and synchronization system for the new PWFA research

Xinpeng MA, Nan Gan, Yajie Mu, Yongyi Peng, Wenbin Gao, Cai Meng, Jingyi Li, Xiaoping Li, Wei Lu

Institute of High Energy Physics, Chinese Academy of Sciences (IHEP-CAS)

Low Level Radio Frequency workshop (LLRF2025), Newport News 2025-10-15

Outline

- IHEP and BEPCII-U (Beijing Electron Positron Collider)
- Plasma WakeField Acceleration(PWFA) at IHEP Upgrade LLRF and phase reference line







BEPCII-U: 2.8GeV E-/E+ Collider / SR























News from High Energy Photon Source (HEPS, 2019-2025)

- 2019/06 Civil starts ✓
- 2022/02 Linac&Booster start to install ✓
- 2023/03 Linac first beam ✓
- 2023/11 Booster passed acceptance ✓
- 2024/07 Storage ring commissioning ✓
- 2024/12 First X-ray •
- 2025/09 Passed acceptance test, in (pre)-operation

Parameters	Acceptance test results
Energy	6.01 GeV
Emittance	56.8 pm
Current	100.5 mA
Orbit stability	19.8% max
Brightness	4×10^{21} phs/s/mm ² /mrad ² /0.1%BW
Energy of X-ray	349.57 keV peak






Outline

- IHEP and BEPCII-U
- Plasma WakeField Acceleration(PWFA) at IHEP Upgrade/new LLRF and phase reference line

PWFA

- PWFA (Plasma WakeField Acceleration) is a beam accelerated by another beam-stimulated wakefield when it pass through a plasma
- Pro: Very high acclerating gradient >10GeV/m!
- High energy physics future: Higgs factory needs e-/e+ collider, CEPC proposal is underway, but still too complex(100km) and expensive, PWFA is a candidate way for future collider and FEL





PWFA and **BEPCII-U**

- BEPCII is an e-/e+ collider from 2005, make it alive and thrive
- BEPCII-U project: upgraded during 2024.07-2025.02, to increase energy from 2.5GeV to 2.8GeV, 3 x higher collision luminosity broadening tau-charm energy region


BEPCII Upgrades:

- upgraded Linac
- 2 more SRF cavities
- new IP magnets
- upgrade in detectors ...
- New PWFA test facility:
 new science and new
 engineering, a new
 150MeV Linac in PWFA
 exp. hall (2024)






- Goal 1. Self PWFA in new photon-cathode Linac by two bunches train. (BL2)
- Goal 2. First PWFA experiment of positron by one driven e-bunch from new Linac and accelerated positron from BEPCII-U Linac. (BL2+BL1)
- Goal 3. First cascaded PWFA of e+/e- by accelerated bunch together with bunch from BEPCII-U Linac based on Goal 1 + Goal 2. (BL2+BL1)
- Goal 4. Laser Plasma Acceleration(LPA): PetaWatts Laser.



1. upgrade of main PRL

- Upgrade/build BEPCII-U/PWFA phase reference lines based on optical fibers, similar tech as HEPS: MO to the Linac(400m), to the PWFA(200m), to the East and West SRF(150m), replacing cables, active feedback of phase drift of fibers
- LMO and RMO are locked with single 10MHz Rb atom clock improving freq stability



master oscillator

power splitter

and amplifier

East SRF West SRF

Phton station

optical fiber

master oscillator 571.2MHz

multiple signal

generator

1. upgrade of main PRL: Tx-Rx pair


- Revised from 499.8MHz on HEPS to 571.2MHz on BEPCII-U
- 2x499.8 Tx-Rx pairs for SRF, 2x571.2MHz for Linac and PWFA







Received RF from MO to Linac via 400m fiber



Specfication				
Center frequency	499.8MHz / 571.2MHz			
Bandwidth	±3MHz@0.01dB ±10MHz@0.1dB			
Input amplitude	>10dBm			
Output amplitude	>12dBm x 2			
Max phase delay range	120ps@0.01dB amp. sta. 540ps@0.1dB amp. sta.			
Additive jitter	<18fs(10Hz-10MHz)			
Long-term stability (out-of-loop)	200fs (p-p)- 3days			
Long-term stability (in-loop)	100fs (p-p) - 7days			
Temperature stability	±0.01°C			
Remote communication	LAN/support EPICS			
Cooling	Conduction cooled, no fans			
Automation	work point recover after power cycle or close/open loop			

Details in LLRF2024 ST WS: "Phase distribution system of HEPS"


- BEPCII-U Linac: 200m, 2 more klystrons, 22 in total, full energy 2.8GeV for electrons and positrons
- Upgrade 22 + 2 new MTCA.4 LLRF 2856MHz system, 2x 142.8MHz and 571.2MHz bunchers system = 24
- Upgrade all signal module TEC-controlled ±0.01K

	1	
PRL <- 8W PA	N	
Phase monitor		
Freq Multiply		
Linac MSG	I	100 mm
-> Optical Rx	N.	HALF U HE
	П	


Frequency	2856 MHz		
Pulse width	4 us		
Klystron	50 MW		
Repetation	1/12.5/25/50 Hz		



Fully MTCA based modenized LLRF








MTCA.4 AMC

- Double width
- local timing and protection
- 8 channels TTL/LVTTL
- in/out direction configurable
- Impedance 50 Ohm/Hi-Z
- Fanout through backplane
- optical 2 in/2 out
- MMC by I2C: voltage, current, temperature monitroring




Downconverter RTM

- MicroTCA.4 RTM, Class A1.1
- 8 channels 600M-6GHz DWC
- □ 8 IF 5-100MHz
- □ 1 channel VM UPC 50M-6GHz
- 2 channels DC input (MMCX)
- LO/REF power monitor
- adjustable in/output attenuation
- 4 channels TTL digital I/O
- connector: SMP




Direct-sampling RTM

- MicroTCA.4 RTM, Class A1.1
- 6 channels DC-600MHz DS
- □ 1 channel VM UPC 50M-6GHz
- dual-PLL, 100M-2GHz input
- □ LO/REF power monitor
- 4 channels TTL digital I/O
- connector: SMP
- I2C interface




- **S-band LLRF Performance**: φ<0.6deg(p-p) and A<1%(p-p), short term error 4 times reduction, PFN type modulators used for klystrons.
- Two new K6A and K12A power sources are solid state modulators, stability are further improved
- Linac beam arrival time and energy stability much better



3. Distribute phase in the PWFA station

- To achieve engineering feasibility of PWFA with two accelerator beams, both shortterm jitter and long-term stability shall be considered very carefully
- On the new Linac and PWFA station, all MSG, EVG, LLRF, BAM electronics are installed in the temperature stabilized cabinet (nVent) by ±0.1°C cooling water
- The phase reference line cables are routed in the temperature controlled duct by ±0.1°C cooling water, the cables with lowest temp-phase coefficient are chosen, Commscope LDF2-50A, <3fs/m/°C, estimated ~30fs(p-p) drift



4. Frequencies of the new Linac

- Have to generate L band and 499.8MHz(for timing EVG) from BEPCII-U(existed 2856MHz)
- Those both L and S band machine, mostly from MO 1300MHz to 2856MHz
- Calculate from 2856MHz to near 1300MHz(because photon-gun been decided L band),
 big enough common frequencies, near 1300MHz as gun can only be very few freq tuned
- Final solution is common frequency 14.28MHz=1/200*2856MHz, L band 1299.48MHz referenced for both L band gun and driven laser

$$\frac{1300}{2856} = \frac{325}{714} = 0.45518207.....$$


$$0.455 = \frac{91}{200}$$

1/2 - 9/200: 1428-14.28*9 = 1299.48

$$0.455 \times 2856 = 1299.48$$


Common frequency: 14.28MHz

Beam line 2: new Linac, beam shall be sync-ed with beam from BEPCII-U Linac



4. Multiple signal generator in the PWFA station

- Each power cycle, signal phases should be restored to easy beam commissioning, so tested and chosen dividers AD9514 (with special phase-reset-pin)
- Common frequencies 14.28MHz and 71.4MHz shall be used as the trigger to monitoring all other frequencies phases using oscilloscope



4. Multiple signal generator in the PWFA station

MSG (9 channels) pannel




- Received signals jitter was measured, L band 26.5fs(10Hz-10MHz)
- Phase recovery was also tested OK!




	In	Out1	Out2	Out3	Out4
Freq/MHz	571.2	85.68	1299.48	1285.2	14.28
jitter/fs (10Hz-10MHz)	16	111.6	26.5	34.2	709
Power/dBm	100	9.1	13.2	14.6	16.5
	Out5	Out6	Out7	Out8	Out9
Freq/MHz	2856	2832.2	95.2	499.8	71.4
jitter/fs (10Hz-10MHz)	32.3	34.5	136.2	59.5	149.7
Power/dBm	13.6	9.6	10.9	15.3	12.5

5. LLRF for PWFA new Linac

- 3 MicroTCA.4 LLRF system, L band(1299.48MHz), S band(2856MHz), X band(11.424GHz)
- Upgrade MicroTCA hardware includes one new 2U local made chassis, in-house made DAQ AMC/DWC RTMs/CPU boards for L&S band, 1 Trig AMC board, NAT MCH
- Firmware/software kept same with BEPCII-U and HEPS



LLRF of L and S band













Summary


IHEP is building a PWFA facility aiming to first positron and cascaded experiments, synchronizing two beams from two Linacs requires upgrade /new of LLRF and phase ref line of the BEPCII-U and PWFA complex

Next step:
Q4/2025 finished PWFA Linac installation
Q1/2026 start PWFA beam

• • • • • •



Thank you for your attenention!



To: maxp@ihep.ac.cn

Xinpeng Ma